


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2545	98-00036-19-FP	WILL	147	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83896

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1	RETAINING WALLS	TRAFFIC SIGNALS 1	TRAFFIC SIGNALS 2	CONSTRUCTION TYPE CODE			NON-PARTICIPATING	
								BOUGHTON RD	104TH ST	BIKE TRAIL	BOLINGBROOK	
				I000-2A	Y007	Y031-IF	Y031-1F	Y046				
60107700	PIPE UNDERDRAINS 6"	FOOT	440	440								
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	841		841							
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	2	2								
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	112	112								
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1								
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	16	16								
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	20	20								
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2								
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13	13								
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	5	5								
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	3	3								
60247900	JUNCTION CHAMBER, SPECIAL	EACH	4	4								
60248000	JUNCTION CHAMBER, NO. 1	EACH	7	7								
60248100	JUNCTION CHAMBER, NO. 2	EACH	6	6								
60255500	MANHOLES TO BE ADJUSTED	EACH	12	12								
60256940	MANHOLES TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2								
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1								
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	4	4								
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3	3								
60500040	REMOVING MANHOLES	EACH	2	2								
60500060	REMOVING INLETS	EACH	4	4								
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	173	173								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	22784	22784								
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	125	125								
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	37.5	37.5								
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1								

- DENOTES SPECIALTY ITEM
- ROADWAY - 80% FEDERAL 20% LOCAL
RETAINING WALLS - 80% FEDERAL 20% LOCAL
NON-PARTICIPATING - 100% LOCAL

WILL COUNTY DEPARTMENT OF HIGHWAYS			
PLAINFIELD-NAPERVILLE ROAD (C.H. 14) ROADWAY RECONSTRUCTION SUMMARY OF QUANTITIES			
 McDonough Associates Inc. Engineers/Architects		DESIGNED BY: CHECKED BY: N.J.L. DRAWN BY: R.E.	SCALE: N.T.S.
NO.	DATE	REVISION	BY