TOTAL SHEET SHEETS NO. FAU 2545 * WILL 147 64 FED.ROAD DIST. NO. 7 BLINOIS FED. AID PROJECT. * 98-00036-19-FP CONTRACT NO. 83896 - INDICATES TEMPORARY PAVEMENT EX ROW 75+00 76+00 77+00 EX ROW NAPERBROOK GOLF COURSE W.S. = 634.5 (NAPERVILLE PARK DISTRICT) WETLAND #1 PK NAIL NORTH FACE OF WOOD ELECTRIC POLE WITH ORANGE FLAGGING NOTE: QUANTITIES HAVE BEEN ESTIMATED FOR 50% OF THE AREA SHOWN HEREIN FOR TEMPORARY EROSION CONTROL SEEDING WHICH WILL BE USED ONLY AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH ARTICLE 280.04(f) OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS INCLUDED HEREIN. THE UNIT PRICES BID FOR ITEMS TEMPORARY EROSION CONTROL SEEDING AND MULCH METHOD 2 SHALL REMAIN CONSTANT THROUGHOUT THE DURATION OF THE CONTRACT REGARDLESS IF THERE IS AN INCREASE OR A DECREASE IN THE QUANTITIES ESTIMATED FOR THESE ITEMS. **LEGEND** INLET & PIPE PROTECTION (TYPICAL) DRN. STRUCTURE INLET FILTER NOTE: TEMPORARY EROSION CONTROL TEMPORARY EROSION CONTROL SEEDING SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH SPECIAL PROVISIONS. TEMPORARY DITCH CHECK SEEDING & MULCH METHOD 2 PERIMETER EROSION BARRIER (SILT FILTER FENCE) AGGREGATE TEMPORARY ACCESS ----- TEMPORARY FENCE G:\20030023 - Plai 07/08/05 - 08:06 WILL COUNTY DEPARTMENT OF HIGHWAYS PLAINFIELD—NAPERVILLE ROAD (C.H. 14) ROADWAY RECONSTRUCTION TEMPORARY EROSION CONTROL — STAGE 1 STA 69+66 TO STA 78+00 DESIGNED BY: JTF CHECKED BY: NJL DRAWN BY: JTF McDonough Associates Inc. Engineers/Architects 1" == 40'

TEC01