

PLAN	SURVEYED BY	DATE	SHEET NO.	TOTAL SHEETS	SECTION	COUNTY	FED. AID PROJECT
NOTE BOOK	ALIGNED	BY	DATE	DATE	DATE	DATE	DATE
NO.	NO.	NO.	NO.	NO.	NO.	NO.	NO.

PROFILE	SURVEYED BY	DATE	SHEET NO.	TOTAL SHEETS	SECTION	COUNTY	FED. AID PROJECT
NOTE BOOK	ALIGNED	BY	DATE	DATE	DATE	DATE	DATE
NO.	NO.	NO.	NO.	NO.	NO.	NO.	NO.

\\fs000001\m0001\010101\1000-1A\1000-1A.dgn

CODE NUMBER	PAY ITEM	UNIT	QUANTITY	H40 1000-1A	H40 Y031-1F	H40 Y030-1E	07N 1000-1A NON-PART.
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MD	14	14			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1856	1856			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	47578	47578			
• 72000100	SIGN PANEL, TYPE 1	SQ FT	327	327			
• 72000200	SIGN PANEL, TYPE 2	SQ FT	49	49			
• 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	7	7			
• 72900100	METAL POST - TYPE A	FOOT	204	204			
• 72900200	METAL POST - TYPE B	FOOT	487	487			
• 78000100	THERMOPLASTIC PAVEMENT MARKING LINE - LETTERS AND SYMBOLS	SQ FT	983	983			
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5837	5837			
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4968	4968			
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	946	946			
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	660	660			
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	693	693			
• 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	573	573			
• 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1380	1380			
• 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	2564	2564			
• 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	309	309			
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	298	298			
• 78300100	PAVEMENT MARKING REMOVAL	SQ FT	13071	13071			
• XX006937	GROUND ROD, 5/8" X 10 FT.	EACH	56			56	
• 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1776		1776		
• 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	118		118		
• 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	63		63		
• 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	177		177		
• 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	20		20		
• 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	473		473		
• 81018700	CONDUIT PUSHED, 3" DIA, GALVANIZED STEEL	FOOT	954			954	
• 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	756		756		
• 81400100	HANDHOLE	EACH	5		5		
• 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4		
• 81400300	DOUBLE HANDHOLE	EACH	3		3		
• 81800400	AERIAL CABLE, 4-1/C NO. 2 WITH MESSENGER WIRE	FOOT	4770			4770	
• 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6628		2067	4561	
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	64			64	
• 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	24			24	
• 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	1			1	
• 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	28			28	
• 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	240			240	
• 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	24			24	
• 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	9			9	
• 84200700	LIGHTING FOUNDATION REMOVAL	EACH	9			9	
• 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1		
• 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1		
• 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	698		698		
• 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2307		980		1327

• INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 56 AT KIRK / FARNSWORTH

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: APR 06 2007

DRAWN BY: BAH
CHECKED BY: APS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83906