

PLAN	DATE	BY	REVIEWED	CHECKED
			PLOTTED	DESIGNED
			ALIGNMENT	FILE NAME
			NO.	

PROFILE	DATE	BY	REVIEWED	CHECKED
			PLOTTED	DESIGNED
			STRUCTURE	NOTATION CHWD
			NO.	

\\p01\share\11462001\4010301.dwg - 11462001.dwg 4/7/2007

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 83906

PAVEMENT SCHEDULE

LOCATION	SIDEWALK REMOVAL		PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	ISLAND PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL 4 1/4"	COMBINATION CONCRETE CURB AND GUTTER REMOVAL		SUBBASE GRANULAR MATERIAL TYPE B, 6"		SUBBASE GRANULAR MATERIAL TYPE B, 8"		AGGREGATE SUBGRADE 12"	POROUS GRANULAR EMBANKMENT SUBGRADE	HOT-MIX ASPHALT BASE COURSE 6"	HOT-MIX ASPHALT BASE COURSE 8"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP	POLYMERIZED HOT-MIX ASPHALT BIND. COURSE IL-19.0, N90	HOT-MIX ASPHALT SURF. COURSE MIX "C", N50	POLYMERIZED HOT-MIX ASPHALT SURF. COURSE MIX "F", N50
	(SQ FT) LEFT	(SQ FT) RIGHT	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT) LEFT	(FOOT) RIGHT	(SQ YD) LEFT	(SQ YD) RIGHT	(SQ YD) LEFT	(SQ YD) RIGHT	(SQ YD)	(CU YD)	(SQ YD)	(SQ YD)	(GAL)	(TON)	(SQ YD)	(TON)	(TON)	(TON)
ILLINOIS ROUTE 56																							
215+36.50 TO 237+55.00		963	13676		67	276		398	572	102	143	177	151	17995	2022			8675	37.6	98	11129.0		2104.8
FARNSWORTH AVENUE																							
115+05.00 TO 125+51.90	1964		2274				6387	971	1055	343	157			5425				3463	19.6	426	4611.3		1093.2
KIRK ROAD																							
127+51.00 TO 135+55.00			2252		219		3923	154	271	106	96			4057	71			2387	12.5	622	3258.0		699.3
DRIVEWAYS																							
SUBTOTAL**				2731		243		1403		524				2232		139	336	1112	4.8		1324.1	53.5	220.8
TOTAL	2927		18202	2731	286	519	10310	4824		1471		328		29709	2093	139	336	15637	74.5	1146	20322.4	53.5	4118.1

LOCATION	PCC SIDEWALK 5 INCH	DETECTABLE WARNINGS	CLASS D PATCHES TYPE II 12 INCH	CLASS D PATCHES TYPE III 12 INCH	AGGREGATE SHOULDERS TYPE B		STRIP REFLECTIVE CRACK CONTROL TREATMENT		HOT-MIX ASPHALT SHOULDERS, 6 1/4"		COMBINATION CONCRETE CURB AND GUTTER TYPE M-6.06		COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12		COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24		CONCRETE MEDIAN SURFACE 4 INCH	CONCRETE MEDIAN TYPE SB-6	TEMPORARY PAVEMENT		TEMPORARY ACCESS PRIVATE ENTRANCE	TEMPORARY ACCESS COMMERCIAL ENTRANCE
	(SQ FT)	(SQ FT)	(SQ YD)	(SQ YD)	(TON) LEFT	(TON) RIGHT	(FOOT) LEFT	(FOOT) RIGHT	(SQ YD) LEFT	(SQ YD) RIGHT	(FOOT) LEFT	(FOOT) RIGHT	(FOOT) LEFT	(FOOT) RIGHT	(FOOT) LEFT	(FOOT) RIGHT	(SQ FT)	(SQ FT)	(SQ YD) LEFT	(SQ YD) RIGHT	(EACH)	(EACH)
ILLINOIS ROUTE 56																						
215+36.50 TO 237+55.00	699	62			75.0	22.5			1080	1151	51				1140	1133	910	4981	177	151		
FARNSWORTH AVENUE																						
115+05.00 TO 125+51.90			60	32			1041	1055					14	24	1527	1384		1638				
KIRK ROAD																						
127+51.00 TO 135+55.00				19			497	221				58			986	1204	266	1548				
DRIVEWAYS																						
SUBTOTAL**													1659				2871			2		2
TOTAL	699	62	60	51	97.5		2814		2231		109		1697		7374		4047	8167	328	2	2	

- * TEMPORARY PAVEMENT FOR MAINTENANCE OF TRAFFIC.
- **SEE DRIVEWAY SCHEDULE FOR INDIVIDUAL DRIVEWAY QUANTITIES.

NOTE:

THE QUANTITY FOR POLYMERIZED HOT-MIX ASPHALT BINDER COURSE ON FARNSWORTH AVENUE AND KIRK ROAD INCLUDES THE AREA WITHIN THE LIMITS OF THE PROPOSED MEDIANS (NECESSARY FOR MAINTENANCE OF TRAFFIC).

DRIVEWAY SCHEDULE

DRIVEWAY LOCATION	DRIVEWAY PAVEMENT REMOVAL	ISLAND PAVEMENT REMOVAL	COMBINATION CONC. CURB & GUTTER REMOVAL	SUBBASE GRANULAR MATERIAL TYPE B, 6"	AGGREGATE SUBGRADE 12"	HOT-MIX ASPHALT BASE COURSE 6"	HOT-MIX ASPHALT BASE COURSE 8"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT BIND. COURSE IL-19.0, N90 (TON)	HOT-MIX ASPHALT SURF. COURSE MIX "C", N50 (TON)	POLYMERIZED HOT-MIX ASPHALT SURF. COURSE MIX "F", N90 (TON)	COMBINATION CONC. CURB & GUTTER TYPE B-6.12 (FOOT)	CONCRETE MEDIAN SURFACE 4 INCH (SQ FT)	TEMPORARY ACCESS PRIVATE ENTRANCE (EACH)	TEMPORARY ACCESS COMMERCIAL ENTRANCE (EACH)
ILLINOIS ROUTE 56																
218+22 RT*				10		9		4			1.0				1	
219+11 RT*				71		68		31			7.7					
221+06 RT	592	49	210		595			241	1.1	356.2		59.4	361	877		
227+41 LT	372	76	236		375			142	0.7	210.4		35.1	334	760		
227+45 RT	480	118	265		461			178	0.8	262.8		43.8	364	1098		
SAVANNAH DRIVE LT	403		271		381			156	0.7	229.9		38.3	205			
SAVANNAH DRIVE RT	441		169		420			179	0.8	264.8		44.2	123			1
237+32 LT				66		62		28			7.0				1	
FARNSWORTH AVENUE																
118+40 LT	240		135	210				185	0.4		20.8		187	136		1
123+40 LT	203		117	167				69	0.3		17.0		85			
SUBTOTAL - DRIVEWAYS	2731	243	1403	524	2232	139	336	1112	4.8	1324.1	53.5	220.8	1659	2871	2	2

- * QUANTITIES INCLUDE PROPOSED MAILBOX TURNOUT.

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 56 AT KIRK / FARNSWORTH

PAVEMENT SCHEDULE
DRIVEWAY SCHEDULE

SCALE: VERT.
HORIZ.
DATE: APR 06 2007

DRAWN BY BAH
CHECKED BY APS