

PLAN	SURVEY	DATE
	NOTED	BY
	ALIGNED	
	CHECKED	
NOTE BOOK	NO.	

PROFILE	SURVEY	DATE
	NOTED	BY
	GRADES CHECKED	
	STRUCTURE NOTATIONS CHKD	
NOTE BOOK	NO.	

\\p01\share\1116001\1031_100_r168\road\1116001_1031_100.dgn
4/7/2007

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83906

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (CU YD)
ILLINOIS ROUTE 56				
215+36.50 TO 223+73.84	5814	4942	498	4444
223+73.84 TO 237+55.00	12534	10654	631	10023
FARNSWORTH AVENUE				
115+05.00 TO 125+51.90	3996	3397	632	2765
KIRK ROAD				
127+51.00 TO 135+55.00	4753	4040	346	3694
TOTAL	27097	23032	2107	20925

SHRINKAGE FACTORS
EARTH EXCAVATION 15%

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 56 AT KIRK / FARNSWORTH

EARTHWORK SCHEDULE

SCALE: VERT.
HORIZ.
DATE: APR 06 2007
DRAWN BY BAH
CHECKED BY APS