

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

MAINTENANCE OF TRAFFIC SCHEDULE

LOCATION	WORK ZONE PAVEMENT MARKING REMOVAL (SQ. FT.)	WORK ZONE PAVEMENT MARKING WET PAVEMENT MARKING TAPE, TYPE III						
		LETTERS AND SYMBOLS (SQ. FT.)	LINE - 4"			LINE - 6"		SOLID STOP BAR WHITE (FOOT)
			SOLID EDGE LINE WHITE (FOOT)	SOLID MEDIAN YELLOW (FOOT)	30' - 10' SKIP-DASH WHITE (FOOT)	SOLID LANE LINE WHITE (FOOT)	6' - 2' SKIP-DASH WHITE (FOOT)	
STAGE I								
IL ROUTE 56 (WEST LEG)	0	72.6	1325	1278		200	38	90
IL ROUTE 56 (EAST LEG)	0	72.6	3197	3176		200	38	78
FARNSWORTH AVENUE	0	72.6	2698	2528	630	200	66	72
KIRK ROAD	0	72.6	1872	1101	420	392	76	140
SUBTOTAL - STAGE I	0	290.4	9092	8083	1050	992	218	380
STAGE II								
IL ROUTE 56 (WEST LEG)	1104	108.9	783	1265		370	64	116
IL ROUTE 56 (EAST LEG)	2355	145.2	2012	2953		611	94	44
FARNSWORTH AVENUE	2194	72.6	1430	2576	640	200	38	78
KIRK ROAD	1508	145.2	1204	1608	410	594	76	297
SUBTOTAL - STAGE II	7160	471.9	5429	8402	1050	1775	272	535
STAGE IIB								
IL ROUTE 56 (WEST LEG)	1067	108.9	649	1416		332	178	74
IL ROUTE 56 (EAST LEG)	2175	254.1	2264	2605		982	234	48
FARNSWORTH AVENUE	203	72.6	509					76
KIRK ROAD	975	108.9	1993	1208	560	859	38	193
SUBTOTAL - STAGE IIB	4419	544.5	5415	5229	560	2173	450	391
STAGE III								
IL ROUTE 56 (WEST LEG)	125	72.6	198	100		98		70
IL ROUTE 56 (EAST LEG)	999	181.5	790	475		401	76	50
FARNSWORTH AVENUE	1844	72.6	1688	2516	640	198	38	70
KIRK ROAD	2530	72.6	1961	1714	470	440	38	160
SUBTOTAL - STAGE III	5498	399.3	4637	4805	1110	1137	152	350
STAGE IV								
IL ROUTE 56 (WEST LEG)	244	36.3	814		170	334	68	
IL ROUTE 56 (EAST LEG)	76		390					
FARNSWORTH AVENUE	59		568					
KIRK ROAD	391	36.3	966		80	428	38	
SUBTOTAL - STAGE IV	770	72.6	2738	0	250	762	106	0
STAGE V								
IL ROUTE 56 (WEST LEG)	1465	145.2	1395	1564	50	650	112	94
IL ROUTE 56 (EAST LEG)	2143	254.1	1640	2364		918	168	214
FARNSWORTH AVENUE	1143	72.6	1299	1145	70	686		34
KIRK ROAD	500	145.2	785		80	192		
SUBTOTAL - STAGE V	5251	617.1	5119	5073	200	2446	280	342
STAGE VI								
IL ROUTE 56 (WEST LEG)	302	36.3	389			26		212
IL ROUTE 56 (EAST LEG)	1055	36.3	1193		30			140
FARNSWORTH AVENUE	2137	108.9	2530	2360	550	406	64	140
KIRK ROAD	1684	72.6	1355	1613	550	200	50	138
SUBTOTAL - STAGE VI	5178	254.1	5467	3973	1130	632	114	630
STAGE VIB								
IL ROUTE 56 (WEST LEG)	36		743	1331		229	68	124
IL ROUTE 56 (EAST LEG)	1385	108.9	1672	2180		96		70
FARNSWORTH AVENUE	402	72.6	612				38	
KIRK ROAD	1327		1166	1613	550	200	50	138
SUBTOTAL - STAGE VIB	3151	181.5	4193	5124	550	525	156	332
STAGE VII								
IL ROUTE 56 (WEST LEG)	1167	145.2	152					62
IL ROUTE 56 (EAST LEG)	2116	326.7	1682	1010	90	1712	234	100
FARNSWORTH AVENUE	360		152					124
KIRK ROAD	96		350			588	50	
SUBTOTAL - STAGE VII	3739	471.9	2336	1010	90	2300	284	286
STAGE VIII								
IL ROUTE 56 (WEST LEG)	992	108.9	424		370		60	140
IL ROUTE 56 (EAST LEG)	1069	181.5	3		260	803	60	102
FARNSWORTH AVENUE	1723	217.8	888	1822	530	430	60	268
KIRK ROAD	2044	145.2	976	2147	650		210	333
SUBTOTAL - STAGE VIII	5828	653.4	2291	3969	1810	1233	390	843
FINAL*								
IL ROUTE 56 (WEST LEG)	1223							
IL ROUTE 56 (EAST LEG)	1264							
FARNSWORTH AVENUE	1837							
KIRK ROAD	2260							
SUBTOTAL - FINAL	6584	0.0	0	0	0	0	0	0
TOTAL	47578	3956.7		100186			20486	

- REMOVAL OF THE WORK ZONE PAVEMENT MARKINGS FROM STAGE VIII.
INCLUDES REMOVAL OF SHORT TERM PAVEMENT MARKINGS PRIOR TO PLACEMENT OF THE PERMANENT STRIPING.

**ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 56 AT KIRK / FARNSWORTH**

MAINTENANCE OF TRAFFIC SCHEDULE

SCALE: VERT.
HORIZ.
DATE APR 06 2007

DRAWN BY BAH
CHECKED BY APS

PLAN	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	ALIGNMENT CHECKED		
	RT. OF WAY CHECKED		
	CADD FILE NAME		

PROFILE	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO. _____	GRADES CHECKED		
	I.B.M. NOTED		
	STRUCTURE NOTATIONS CHKD		

yztejcb6am!thw200!m010321_ko_r!t656woodw!n_cwgs32!_ach07.dgn