F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	01-00273-00-CH	KANE	172	86
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83906

SCALE IN FEET

NOTE:
ALL DESIGNATED SOD AREAS SHALL BE IRRIGATED. THE CONTRACTOR SHALL PROVIDE ALL DESIGN DETAILS, CALCULATIONS, PLANS, SHOP DRAWINGS, AND ALL LABOR, MATERIAL, EQUIPMENT AND SERVICES NECESSARY FOR CONSTRUCTION OF THE LANDSCAPE IRRIGATION SYSTEM (SEE SPECIAL PROVISIONS).

THE CONTRACTOR SHALL PROVIDE IRRIGATION SYSTEM DESIGN DETAILS, CALCULATIONS, PLANS, AND SHOP DRAWINGS TO THE CITY OF AURORA FOR REVIEW PRIOR TO INSTALLATION.

PLAN
DATE / BY
SURVEYED
PLOTTED
ALIGNMENT CHECKED
PTS. OF BEG. CHECKED
NOTE BOOK
NO.
ROAD FILE NAME

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
SHAL NOTED
NOTE BOOK
NO.
STRUCTURE NO'S/ATN'S CHKD

PROPOSED STORM SEWER (TYP.)
161 CAOV
37 LIN FT TYPE K COPPER PIPE 2"
STA 120+46.50, 0.00' LT/RT
IRRIGATION SERVICE LOCATION
2" VALVE AND 4' DIA. VALVE VAULT•
RIM = 738.30
673 PORE
157 SEAJ
EXISTING 12" WATER MAIN
5 QUBI
SODDING, SALT TOLERANT (541 SQ YD)
LIMESTONE MASONRY (3 CU YD)
450 PORE
222 CAOV
1 GIBI
LIMESTONE MASONRY (3 CU YD)
208 CAOV
760 PORE
12" WATER
120
125
225

ABBREVIATIONS-PLANT LIST

1. SHADE
   - ACPL - TREE, ACER PLATANOIDES (NORWAY MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED (8 EACH)
   - GIBI - TREE, GINKGO BILBOA AUTUMN GOLD (AUTUMN GOLD GINKGO), 2-1/2" CALIPER BALLED AND BURLAPPED (2 EACH)
   - QUBI - TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED (5 EACH)
2. PERENNIALS
   - PORE - VINE-POLYGONUM REYNOUTRIA (DWARF FLEECE FLOWER) (4394 EACH)
   - SEAJ - SEDUM 'AUTUMN JOY' (1 GAL) (693 EACH)
3. ORNAMENTAL GRASSES
   - CAOV - CALAMAGROSTIS ACUTIFLORA 'KARL FOERSTER' (1 GAL) (915 EACH)
   - SODDING, SALT TOLERANT (1356 SQ YD)
4. LIMESTONE MASONRY (18 CU YD)

• RPZ BACKFLOW PREVENTOR AND WATER METER INSTALLED IN VALVE VAULT BY OTHERS

STA. 134+00, 59' LT
VALVE AND 4' DIA. VALVE VAULT•
(INSTALLED BY OTHERS)
2" SERVICE LINE
(BY OTHERS)
STA 134+00 0' LT/RT
STUB AND CAP
(PROVIDED BY OTHERS)
IRRIGATION SERVICE LOCATION
400 PORE
99 CAOV
4 ACPL
LIMESTONE MASONRY (3 CU YD)
LIMESTONE MASONRY (4 CU YD)
130
135
24" CMP
12" SAN
ADS 21
225
157 CAOV
638 PORE
291 SEAJ
1 GIBI
640 PORE
68 CAOV
SODDING, SALT TOLERANT (815 SQ YD)
LIMESTONE MASONRY (5 CU YD)
833 PORE
4 ACPL
245 SEAJ

• RPZ BACKFLOW PREVENTOR AND WATER METER INSTALLED IN VALVE VAULT BY OTHERS

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 56 AT KIRK / FARNSWORTH

MEDIAN LANDSCAPING PLAN (KIRK ROAD/FARNSWORTH AVENUE)

SCALE: VERT.
HORIZ.
DATE APR 06 2007

DRAWN BY BAH
CHECKED BY APS

X:\PW_DOCS\MEP\1744200\MD10221.ACL/*RECS\ADSMITH_DWG*521_1401.dgn