

DE067

FOR SIGNS NOTED TO BE MODIFIED, THE CONTRACTOR WILL ORDER THE INDIVIDUAL PANELS OR FULL PANELS, WHICH EVER IS REQUIRED, TO INSTALL INTO THE SIGN TO HAVE THE FACE OF THE SIGN READ AS STATED FOR THE PROPOSED SIDE A AND SIDE B IN THE GUIDANCE SIGN

FOR SIGNS NOTED TO BE EXTENDED AND MODIFIED, THE CONTRACTOR WILL EXTEND THE SIGN BASE TO ACCOMODATE THE ADDITIONAL MODULE NECESSARY FOR PLACEMENT OF THE SIGN PANEL CHANGES PROPOSED. THE SIGN EXTENSION WILL INCLUDE THE INSTALLATION OF THE ADDITIONAL MODULE AND SIGN PANEL MODIFICATIONS AND PAID FOR UNDER ITEM AR800401 ADD 1 MODULE WITH SIGN BASE EXTENSION, PER EACH. THE ORDER THE INDIVIDUAL PANELS OR FULL PANELS, WHICH EVER IS REQUIRED, TO INSTALL INTO THE SIGN TO HAVE THE FACE OF THE SIGN READ AS STATED FOR THE PROPOSED SIDE A AND SIDE B IN THE GUIDANCE SIGN DATA TABLE.

- BOTH STANDARD (LUMACURVE) AND AGM SIGNS EXIST ON THE AIRFIELD. THE CONTACTOR WILL VERIFY THE SIGN MANUFACTURER. THE CONTRACTOR WILL REMOVE THE EXISTING SIGN
- REMOVED SIGNS, TRANSFORMERS, AND SIGN PANELS WILL BE TURNED OVER TO THE AIRPORT DIRECTOR. PROVIDING THE DIRECTOR DOES NOT WANT THE SALVAGED MATERIALS, THE
- ALL DISTURBED AREAS, AS A RESULT OF THE REMOVALS, WILL BE REGRADED, HOLES FILLED WITH TOP SOIL MATERIAL, SMOOTH GRADED, SEEDED AND FERTILIZED ACCORDING TO
- AR125470 "MODIFY EXISTING SIGN PANEL"____PER EACH. AR800401 "ADD 1 MODULE WITH SIGN BASE EXTENSION".....

ILLINO DECATUR,

802-07RWY R-122CON. 1*=300' 12/01/06 HANSON

RECONSTRUCT A
PORTION OF RUNWAY
6/24, TAXIWAY A AND C
PROPOSED GUIDANCE SIGN
MODIFICATIONS & SIGN DATA