

										100% STATE								100% STATE								100% STATE				100% STATE			
CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	0001		0003		0004		0005		0008				0028	0021		0021				0031		0021	0040	0043		0044			
					ROADWAY		ROADWAY		ROADWAY		ROADWAY		BRIDGE				PATH	LIGHTING		TRAFFIC SIGNALS				LANDSCAPING		SAFETY	RETAIN ING WALLS	UTILITIES		CREEK RELOCATE			
					100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080		STATE	100% LOCAL	EDGE WOOD DRIVE	HUNT INGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCO NNECT	STATE	100% LOCAL			STATE	LOCAL		STATE	LOCAL	
○ K0013090	PERENNIAL PLANTS, WOODLAND TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	8																									8					
○ K1004572	PRAIRIE SEEDING (SPECIAL)	ACRE	2.25																			2.25											
○ K1005875	TREE TRANSPLANT	EACH	6																			6											
• XZ127900	RETAINING WALL REMOVAL	FOOT	2883		30		1325		14																1166			348					
• X0301423	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ FT	9670																						9670								
• X0301797	GATE REMOVAL	EACH	2		2																												
• X0301852	DEWATERING STRUCTURE NO. 1	EACH	1																									1					
• X0321620	SANITARY SEWER REMOVAL 21"	FOOT	13				13																										
• X0322208	TEMPORARY STORM SEWER PLUGS	EACH	3				3																										
• X0323045	STONE OUTCROPPING	SQ FT	690																			690											
• X0323716	ACCESS GATE, DOUBLE, 30 FOOT	EACH	1		1																												
• X0323760	SANITARY SEWER SERVICE, 6" PVC, COMPLETE	EACH	6																							6							
• X0324056	REMOVAL OF EXISTING WOOD BOLLARDS	EACH	47						47																								
• X0324062	ENTRANCE SIGN	L SUM	1		1																												
Δ • X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	5451																225	744	2204	1652	626										
• X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	10605																						10605								
* X0324534	REMOVE AND REINSTALL LIGHT	L SUM	1		1																												
• X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	843																557			286											
• X0325110	BIAXIAL GEOGRID	SQ YD	1445										1445																				
• X0325751	DRIVING SOLDIER PILES	FOOT	172																						172								
• X0326694	PLUG EXISTING STORM SEWERS	CU YD	5				5																										
• X0326744	PLUG PIPE PENETRATION	EACH	3				3																										
• X0326805	FOUNDATION REMOVAL	SQ FT	19445		19445																												
• X0326864	BRICK SIDEWALK REMOVAL	SQ FT	425		172				253																								
• X0327036	BIKE PATH REMOVAL	SQ YD	2200		1359		841																										
• X0327301	RELOCATE EXISTING MAILBOX	EACH	14		1		12		1																								
• X0327371	PLUG EXISTING PIPE	CU YD	0.5						0.5																								
• X0350805	FOLD DOWN BOLLARDS	EACH	17				17																										
• X0350810	BOLLARD REMOVAL	EACH	3						3																								

• INDICATES SPECIAL PROVISION
Δ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
□ ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

Rev. 6-6-12