

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY AND DRAINAGE	RETAINING WALL SN 022-W045	PUMP STATION 47
				0004 URBAN	0040 URBAN	0040 URBAN
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	16,230		16,230	1
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	6,600		6,600	1
X0325405	FILL EXISTING STORM SEWERS	CU YD	67	67		
X0326694	PLUG EXISTING STORM SEWERS	CU YD	0.5	0.5		
X0335700	PUMP STATION GENERAL WORK	L SUM	1			1
* X0783300	PUMP STATION ELECTRICAL WORK	L SUM	1			1
* X0783500	PUMP STATION MECHANICAL WORK	L SUM	1			1
X2020502	BRACED EXCAVATION	CU YD	2,730			2,730
X4402302	CURB REMOVAL (PARTIAL)	FOOT	170	170		
X6028050	TEMPORARY MANHOLE	EACH	5	5		
* X6640308	CHAIN LINK GATES, (SPECIAL)	EACH	3	3		
* X6640570	CHAIN LINK FENCE, 8' (SPECIAL)	FOOT	143	143		
* X6640585	CHAIN LINK FENCE, ATTACHED TO STRUCTURE, SPECIAL	FOOT	105	105		
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	20	20	1	
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	356	356		

* SPECIALTY ITEM

1 Rev. 6-4-12

	USER NAME : USER#	DESIGNED - DMS	REVISED - 04-06-2012	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE:	SHEET NO. 1 OF 6 SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE : #SCALE#	DRAWN - KEA	REVISED -							338/IL 59	2011-035-I	DUPAGE	181	68
	PLOT DATE : #DATE#	CHECKED - PJO	REVISED -							CONTRACT NO. 60P41				
		DATE - 03-22-2012	REVISED -							ILLINOIS FED. AID PROJECT				