


| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONST. CODE |
|----------|--|------|----------------|---------------|
| | | | | 100% STATE |
| | | | | DRAINAGE |
| | | | | 0044 URBAN |
| 550A0330 | STORM SEWERS, CLASS A, TYPE 2 10" | FOOT | 131 | 131 |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 14 | 14 |
| 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | FOOT | 456 | 456 |
| 550A0380 | STORM SEWERS, CLASS A, TYPE 2 18" | FOOT | 40 | 40 |
| 55100400 | STORM SEWER REMOVAL 10" | FOOT | 133 | 133 |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 8 | 8 |
| 55100900 | STORM SEWER REMOVAL 18" | FOOT | 40 | 40 |
| 60200205 | CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 |
| 60200805 | CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 8 GRATE | EACH | 2 | 2 |
| 60201340 | CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 24 FRAME AND GRATE | EACH | 2 | 2 |
| 60208240 | CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE | EACH | 3 | 3 |
| 60250200 | CATCH BASINS TO BE ADJUSTED | EACH | 1 | 1 |
| 60500050 | REMOVING CATCH BASINS | EACH | 4 | 4 |
| 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 232 | 232 |

* SPECIALTY ITEM

FILE NAME = S:\JULI_VS300-6339\6346\035\Micro\CP00_Sheets\0168639.plt-500.dgn



| | | |
|-----------------------------|----------------|-----------|
| USER NAME = dennisw | DESIGNED - TJS | REVISED - |
| | DRAWN - DJW | REVISED - |
| PLOT SCALE = 20.0000' / in. | CHECKED - MAG | REVISED - |
| PLOT DATE = 4/2/2012 | DATE - 4-2-12 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-55 NORTHBOUND EXIT RAMP
SUMMARY OF QUANTITIES

SCALE: N/A SHEET 3 OF 4 SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|----------|--------|--------------------|-----------|
| 55 | 112-636T | COOK | 36 | 6 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 60T37 | |