- 2. THE TERM "VILLAGE" USED HEREIN IN REFERENCE TO NOTIFICATION(S) BY OR PERMIT(S)/PERMISSION(S) TO BE OBTAINED BY THE CONTRACTOR SHALL MEAN THE MUNICIPAL OFFICIAL DULY DESIGNATED BY THE VILLAGE BOARD FOR THE PURPOSE. THE CONTRACTOR SHALL CONTACT THE VILLAGE MANAGER'S OFFICE AT (708) 335-9600 TO GET THE NAME(S) AND CONTACT INFORMATION OF SUCH DESIGNATED OFFICIALS/STAFF.
- 3. A MINIMUM OF TWO (2) WORKING DAYS BEFORE STARTING EXCAVATION, THE CONTRACTOR SHALL CONTACT JULIE (1-800-892-0123 OR 811) TO HAVE THE LOCATION OF EXISTING UNDERGROUND UTILITIES STAKED OR OTHERWISE MARKED AT THE SITE.
- 4. IF AND WHEN EXISTING DRAINAGE FACILITIES ARE DISTURBED BY PROPOSED CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY CHITLETS AND CONNECTIONS FOR ALL PRIVATE AND PUBLIC DRAINS, SEWERS OR CATCH BASINS, AND PROVIDE ADEQUATE FACILITIES TO TAKE IN ALL STORM WATER INCLUDING PUMPING AND A TEMPORARY OUTLET. IF NECESSARY, THIS WORK SHALL NOT BE PAID FOR DIRECTLY, BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 5. THE CONTRACTOR SHALL MAKE EVERY POSSIBLE EFFORT TO PREVENT CONSTRUCTION DEBRIS FROM ENTERING EXISTING MANHOLES, CATCH BASINS, INLETS OR DRAINAGE DITCHES. ANY SUCH DEBRIS. DETERMINED BY THE VILLAGE TO BE PRESENT IN SUCH STRUCTURES DUE TO THE CONTRACTOR'S OPERATIONS SHALL BE PROMPLTLY REMOVED AND DISPOSED OFF BY THE CONTRACTOR TO THE VILLAGE'S SATISFACTION AT NO ADDITIONAL COMPENSATION.
- 6. ALL REMOVAL OF CURB AND GUTTER, SIDEWALK, DRIVEWAYS AND PAVEMENT ETC. SHALL BE BY SAWCUTTING TO ENSURE A CLEAN REMOVAL WITHOUT DAMAGING OR GAUGING THE PORTION(S) TO REMAIN. ALL SUCH DAMAGE OR GAUGING SHALL BE REPAIRED BY THE CONTRACTOR TO THE VILLAGE'S SATISFACTION WITHOUT ANY ADDITIONAL COMPESATION. THE SAWCUTTING SHALL NOT BE COMPENSATED FOR SEPARATELY BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE REMOVAL OF THE ITEM INVOLVED.
- 7. THE CONTRACTOR SHALL MAINTAIN AT ALL TIMES ADEQUATE ACCESS TO ALL PROPERTIES ADJACENT TO THE PROPOSED IMPROVEMENT. THE COST OF THIS WORK SHALL NOT BE COMPENSATED FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS REMOVAL ITEMS.
- 8. ALL UTILITIES AND THE ASSOCIATED DATA SHOWN ON THE PLANS ARE FROM THE AVAILABLE RECORDS AND REPRESENT THE BEST AVAILABLE INFORMATION. HOWEVER, THEIR ACCURACY OR COMPLETENESS IS NOT GUARANTEED. IT SHALL REMAIN THE CONTRACTOR'S RESPONSIBILITY TO CONTACT JULIE (1-800-892-0123 OR 811) AND VARIOUS UTILITY FIRMS AND/OR ORGANIZATIONS HAVING FACILITIES AT THE SITE TO DETERMINE THEIR ACTUAL LOCATIONS, AND OTHER DETAILS, AND DETERMINE WHETHER THEY ARE IN CONFLICT WITH THE PROPOSED WORK. THE CONTRACTOR SHALL BRING ALL SUCH CONFLICTS TO THE ENGINEER'S ATTENTION AND SHALL NOT PROCEED WITH THE PORTION OF THE WORK IN CONFLICT UNTIL THE RESOLUTION OF THE CONFLICT(S) AND THE AUTHORIZATION TO PROCEED.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT LIMITS, WHETHER OR NOT SUCH UTILITIES ARE SHOWN ON THE PLANS. ANY UTILITY DAMAGED DURING CONSTRUCTION, SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE ENGINEER, BY THE CONTRACTOR WITHOUT ANY ADDITIONAL COMPENSATION.
- 10. THE CONTRACTOR SHALL PROVIDE ADEQUATE PROVISIONS FOR PEDESTRIAN TRAFFIC THROUGH THE CONSTRUCTION AREA AT ALL TIMES AND SEEK THE VILLAGE'S PERMISSION FOR ANY UNAVOIDABLE OBSTRUCTION(S) TO SUCH TRAFFIC.
- 11. LOCAL ACCESS ON ALL SECONDARY STREETS MUST BE MAINTAINED AT ALL TIMES BY THE CONTRACTOR WHEN CONSTRUCTION IS NOT TAKING PLACE AT SUCH LOCATION. ALL TRAFFIC OBSTRUCTIONS TO SUCH STREETS SHALL BE REMOVED ON WEEKENDS. HOLIDAYS AND OVERNIGHT, UNLESS SPECIFICALLY AND EXPLICITLY PERMITTED BY THE VILLAGE.

DISTRICT 1 DETAILS

DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING, BD-8 BUTT JOINT AND HMA TAPER DETAILS, BD-32, DISTRICT ONE DISTRICT ONE, TYPICAL PAVEMENT MARKINGS, TC-13

Globetrotters ENGINEERS - ARCHITECTS 300 S Wacker Drive Chicago, Illinois 60606 U.S.A. Ph 312-922-6400

USER NAME = boris.shkolnik	DESIGNED - CST	REVISED
	DRAWN - BS	REVISED -
PLOT SCALE = N.T.S.	CHECKED - CST	REVISED ~
PLOT DATE = 2/1/2012	DATE -	REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

								_		
PAVEMENT RESURFACING PLAN		F.A. SECTION		COUNTY	TOTAL	SHEET NO.				
GENERAL NOTES, IDOT STANDARDS & SUMMARY OF QUANTITIES			2835 10-00079-00-RS		COOK	10	2			
			CALIFORNIA AVE.		CONTRACT	NO. 6.	370/			
	SCALE: N.T.S.	SHEET NO. 2 OF 10 SHEETS	STA. 50+50	TO STA. 75+60	FED. RC	DAD DIST. NO.	ILLINOIS FED. A	ID PROJECT		

SUMMARY OF QUANTITIES

	CODED ITEM NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
Ī	20200100	EARTH EXCAVATION	CU YD	65	0005
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	250	00 <i>05</i>
	25200100	SODDING	SQ YD	250	0005
ſ	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	990	0005
ſ	40600300	AGGREGATE (PRIME COAT)	TON	20	0005
	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	450	0005
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	625	0005
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	850	0005
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	590	0005
	42400800	DETECTABLE WARNINGS	SO FT	95	0005
	44000500	COMBINATION CURB AND GUTTER REMOVAL	F00T	340	0005
	44000600	SIDEWALK REMOVAL	SO FT	590	0005
	44201747	CLASS D PATCHES, TYPE IV. 8 INCH	SQ YD	980	0005
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	0005
	60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	0005
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	0005
ſ	60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	1	0005
	60611811	COMBINATION CONCRETE CURB AND GUTTER, TYPE M (MODIFIED)	F00T	340	0005
	67100100	MOBILIZATION	L SUM	1	0005
Ī	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0005
ſ	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	00 <i>05</i>
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	F00T	1,010	0005
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	250	0005
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	F00T	150	00 <i>05</i>
	LR400510	REJUVENATING AGENT	GALLON	990	0005
*	LR400520	HOT IN-PLACE RECYCLING-SURFACE RECYCLING	SQ YD	9, 900	0005
*	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3, 550	0005
	XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	10	0005
	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT. 3"	SO YD	15	0005
	Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	20	0005
	Z0004544	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ: YD	40	0005
Ī	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	ĆU YD	65	0005
٠		* SPECIALITY ITEMS			***************************************

IDOT STANDARDS

STANDARD NO.	NAME OF STANDARD
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
424001-06	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C & D PATCHES
604001-03	FRAME AND LIDS TYPE 1
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701301-04	LANE CLOSURE 2L, 2W SHORT TIME OPERATION
701501-06	URBAN LNE CLOSURE, 2L, 2W, UNDIVIDED
701801-05	SIDEWALK CORNER OR CROSSWALK CLOSURE
701901-02	TRAFFIC CONROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS