EARTHWORK SCHEDULE

SUITABLE EXCAVATION (EARTH EXCAVATION)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SUITABLE EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION)
CU YD	CU YD	CU YD	CU YD
469	352	616	-264

TREE REMOVAL SCHEDULE

LOCATION			6 TO	OVER
	OFFSET		15 UNITS	15 UNITS
STATION	LT	RT	DIAMETER	DIAMETER
114+00		20	15	
114+10		15	15	
114+20		10		17
114+40		10	7	
114+45		8	15	
114+60		6		20
114+65	3		15	
114+68	0		15	
114+80	12			17
114+85	5		10	
115+04	0		12	
115+00		18		18
115+15		10	15	
115+18		15	10	
115+22		9	12	

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY 0028
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	141
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	72
	20101100	TREE TRUNK PROTECTION	EACH	3
	20200100	EARTH EXCAVATION	CU YD	469
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,419
	20400800	FURNISHED EXCAVATION	CU YD	264
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,591
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4,350
	25000210	SEEDING, CLASS 2A	ACRE	0.1
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	103
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	103
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	103
	25100630	EROSION CONTROL BLANKET	SQ YD	5538
	28000305	TEMPORARY DITCH CHECKS	FOOT	150
	28000400	PERIMETER EROSION BARRIER	FOOT	4120
	28000500	INLET AND PIPE PROTECTION	EACH	4
	28100103	STONE RIPRAP, CLASS A2	SQ YD	31
	28200200	FILTER FABRIC	SQ YD	2,396
	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2396
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	244
	42001300	PROTECTIVE COAT	SQ YD	32
	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	222
	42400800	DETECTABLE WARNINGS	SQ FT	80
	542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	96
	542C0235	PIPE CULVERTS, CLASS C, TYPE 1 30"	FOOT	45
	54215547	METAL END SECTIONS 12"	EACH	8
	54215565	METAL END SECTIONS 30"	EACH	2
	67100100	MOBILIZATION	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
*	72000100	SIGN PANEL - TYPE 1	SQ FT	28.0
*	72900100	METAL POST - TYPE A	FOOT	20
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	300
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,985
*	X0321322	DROP GATE	EACH	4
*	XX007920	LANDSCAPING STONE	TON	4

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY 0028
*	A2005120	TREE, JUGLANS NIGRA (BLACK WALNUT), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1
*	A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2
*	A2006720	TREE, QUERCUS MACROCARPA (BUR OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2
*	A2007820	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5
*	B2000900	TREE, AMELANCHIER ARBOREA (DOWNY SERVICEBERRY), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3
*	B2001164	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3
*	K1004572	PRAIRIE SEEDING (SPECIAL)	ACRE	0.4
*	K1005421	SEEDING (SPECIAL)	ACRE	0.4
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	16
	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	SQ YD	52

* SPECIALTY ITEM

FILE NAME = $FILE$

URS

USER NAME = $USER$	DESIGNED JIF	REVISED -	
	DRAWN KJB	REVISED -	
PLOT SCALE = $SCALE$	CHECKED DDL	REVISED -	
PLOT DATE = $DATE$ $TIME$	DATE 4/10/12	REVISED -	

ILLINOIS DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES / SCHEDULES

SHEET NO. 1 OF 1 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-F3000-10-BT	DUPAGE	20	3
		CONTRACT NO. 63710		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		