

90% FED.  
10% STATE

SUMMARY OF QUANTITIES		CONSTR. CODE	
		BUREAU COUNTY ROADWAY 0021 RURAL	UNIT
CODE NO.	ITEM		
20200100	EARTH EXCAVATION	CU YD	86
20400800	FURNISHED EXCAVATION	CU YD	2279
25000210	SEEDING, CLASS 2A	ACRE	6.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	594
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	594
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	594
25100630	EROSION CONTROL BLANKET	SQ YD	32004
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	657
28000305	TEMPORARY DITCH CHECKS	FOOT	108
28000400	PERIMETER EROSION BARRIER	FOOT	4500
28000500	INLET AND PIPE PROTECTION	EACH	2
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	660
50300225	CONCRETE STRUCTURES	CU YD	10.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	930
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	287.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	18
64301090	ATTENUATOR BASE	SQ YD	492
X6015000	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2
67100100	MOBILIZATION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CALMO	2
Z0005216	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SO YD	232.4

FILE NAME =	USER NAME = Fergusonse	DESIGNED -	REVISED -
et:\pwwork\pwwork\Fergusonse\0291012\0291012-036898-sh1-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
180	03 IMPACT ATTENUATOR 2012-1	BUREAU	53	3
CONTRACT NO. 66B98				
ILLINOIS FED. AID PROJECT				

Rev.