

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				LIVINGSTON	GRUNDY
				ROADWAY	ROADWAY
				0021	0021
				RURAL	RURAL
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17,190	9870	7320
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	0	1
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	20	0	20
63200310	GUARDRAIL REMOVAL	FOOT	432	432	0
63400105	GUARD POSTS	EACH	2	2	0
64300370	IMPACT ATTENUATORS (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	2	0
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	26	19	7
64301090	ATTENUATOR BASE	SQ YD	751	559	192
X6015000	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	0	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	2	1
67100100	MOBILIZATION	L SUM	1	0.7	0.3
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.5	0.5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	2	1
X6320157	CLEANING UNDERDRAIN OUTLETS	EACH	1	0	1

90% FED.  
10% STATE

FILE NAME =	USER NAME = quigleyml	DESIGNED -	REVISED -
c:\pwwork\pwwork\quigleyml\d0294440\036601-sh-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 * / in.	CHECKED -	REVISED -
	PLOT DATE = 3/30/2012	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	**	96	4
** LIVINGSTON/GRUNDY			CONTRACT NO. 66C01	
[ILLINOIS] FED. AID PROJECT				

\* IMPACT ATTENUATORS 2012-3 *Rev.*