



UNDRGRD C MD
465 FT.

UNDRGRD C MD
778 FT. (PUSHED)
ALONG CEMENTARY
AND UNDER STRUCTURE

COMMUNICATIONS VAULTS
1.0 EACH

UNDRGRD C MD
356 FT.

UNDRGRD C MD
35 FT. (PUSHED)

67

CO RD 1200 E

N 1950th Rd

SCHEDULE OF QUANTITIES		
ITS FIBER (US 67 FROM MACOMB TO MONMOUTH) - SHEET 22		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1634.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1684.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google
Image Map
McDonough County GIS Consortium

Google earth

Imagery Date: 3/31/2010 1998

40°33'58.15" N 90°40'23.30" W elev 709 ft

Eye alt 2794 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 1-109 (Macomb to Monmouth) - Final	DRAWN2.dgn	CHECKED -	REVISED -
	PLOT SCALE = 171.6216 ' / in.	DATE -	REVISED -
	PLOT DATE = 4/23/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
US 67 (FROM MACOMB TO MONMOUTH) CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	25
			CONTRACT NO. 68B03	
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 22 OF 106 SHEETS STA. TO STA.