



UNDRGRD C MD
1493 FT.

THERE ARE DRAINAGE STRUCTURES THAT ARE NOT SHOWN ON THIS SHEET. THE CONTRACTOR SHOULD BE ABLE TO TRENCH AROUND THESE STRUCTURES, HOWEVER, THIS INFORMATION IS BEING PROVIDED FOR REFERENCE ONLY AND THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS PRIOR TO BIDDING.

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 4		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1493.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1493.0

© 2011 Google
Image © 2011 GeoEye

Google earth

Imagery Date: 7/12/2009 1998

40°59'38.44" N 90°20'07.04" W elev 813 ft

Eye alt 2793 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -	FDRAWN 9-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 163.0405' / in.	DATE -	REVISED -
	PLOT DATE = 4/24/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED
SCALE: SHEET NO. 4 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	161
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B03	