



KNOX RD. 2000N

KNOX RD. 2000N

UNDRGRD C MD  
78 FT.

UNDRGRD C MD  
98 FT. (PUSHED)  
UNDER ROADWAY

UNDRGRD C MD  
378 FT.

COMMUNICATIONS VAULT  
1.0 EACH

UNDRGRD C MD  
987 FT.

Knox Rd 560 E

© 2011 Google  
Image © 2011 GeoEye

Google earth

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 6		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1541.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1591.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 7/12/2009 1998

41°00'07.14" N 90°20'05.99" W elev 823 ft

Eye alt 2793 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -	FDRAWN 9-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 163.0405' / in.	DATE -	REVISED -
	PLOT DATE = 4/24/2012		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT  
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED

SCALE: SHEET NO. 6 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	163
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B03	