



COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
616 FT.

UNDRGRD C MD
909 FT.

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 16		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1525.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1575.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google
Image © 2011 GeoEye

Google earth

Imagery Date: 7/12/2009 1998

41°02'31.01" N 90°20'03.24" W elev 833 ft

Eye alt 2793 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -	FDRAWN 9-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 163.0405' / in.	DATE -	REVISED -
	PLOT DATE = 4/24/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED

SCALE: SHEET NO. 16 OF 49 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	173
CONTRACT NO. 68B03			ILLINOIS FED. AID PROJECT	