



UNDRGRD C MD
1221 FT.

COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
309 FT.

THERE ARE DRAINAGE STRUCTURES THAT ARE NOT SHOWN ON THIS SHEET. THE CONTRACTOR SHOULD BE ABLE TO TRENCH AROUND THESE STRUCTURES, HOWEVER, THIS INFORMATION IS BEING PROVIDED FOR REFERENCE ONLY AND THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS PRIOR TO BIDDING.

SCHEDULE OF QUANTITIES		
ITS FIBER (GALESBURG TO WOODHULL) - SHEET 19		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1530.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1580.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google
Image © 2011 GpoEye

Google earth

Imagery Date: 7/12/2009 1998

41°03'14.15" N 90°20'01.07" W elev 808 ft

Eye alt 2793 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\erics plans\68B03 - D4 Fiber Project Sheets 158-206 (Galesburg to Woodhull) -	FDRAWN 9-12.dgn	CHECKED -	REVISED -
	PLOT SCALE = 163.0405' / in.	DATE -	REVISED -
	PLOT DATE = 4/24/2012		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM GALESBURG TO WOODHULL) CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2012	VARIOUS	220	176
CONTRACT NO. 68B03				
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 19 OF 49 SHEETS STA. TO STA.