



UNDRGRD C MD
230 FT.

UNDRGRD C MD
915 FT. (PUSHED)
UNDER ROADWAY AND
ALONG ROUGH TERRAIN
AND TREE GROVES

A COMBINATION OF PUSHED AND TRENCHED
CONDUIT WILL BE REQUIRED IN THIS AREA OF
ROUGH TERRAIN. THE CONTRACTOR SHALL VERIFY
ALL FIELD CONDITIONS PRIOR TO BIDDING.

I-74 EB

I-74 WB

N. 300TH AVE.

N 300th Ave

N. 300TH AVE.

UNDRGRD C MD
418 FT. (PUSHED)
ALONG TREE GROVES

SCHEDULE OF QUANTITIES

ITS FIBER (WOODHULL TO MOLINE) - SHEET 5

UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1563.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1563.0

Imagery Date: 9/12/2011 1993

41°11'35.52" N 90°19'53.82" W elev 803 ft

Eye alt 2791 ft

© 2011 Google

Google earth

FILE NAME =	USER NAME = howalder	DESIGNED -	REVISED -
S:\GEN\DRAW\ITS Fiber Project\68B04\68B04 - Woodhull to Moline (1-95) - Final 4-30-12.dwg		DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM WOODHULL TO MOLINE) CONTINUED**

SCALE: SHEET NO. 5 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	8
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				