



UNDRGRD C MD
352 FT.

UNDRGRD C MD
575 FT. (PUSHED)
ALONG ROUGH TERRAIN

A COMBINATION OF PUSHED AND TRENCHED
CONDUIT WILL BE REQUIRED IN THIS AREA OF
ROUGH TERRAIN. THE CONTRACTOR SHALL VERIFY
ALL FIELD CONDITIONS PRIOR TO BIDDING.

N 600th Ave N. 600TH AVE.

UNDRGRD C MD
654 FT.



I-74

©2011 Google

Google earth

SCHEDULE OF QUANTITIES		
ITS FIBER (WOODHULL TO MOLINE) - SHEET 15		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1581.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1581.0

Imagery Date: 9/12/2011 1993

41°14'05.17" N 90°19'53.09" W elev 784 ft

Eye alt 2791 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (1-95) - Final 4-30-12.dgn	DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/1/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM WOODHULL TO MOLINE) CONTINUED

SCALE: SHEET NO. 15 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	18
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				