



UNDRGRD C MD
781 FT.

UNDRGRD C MD
83 FT. (PUSHED)

UNDRGRD C MD
734 FT.

I-74

© 2011 Google

Google earth

Imagery Date: 9/12/2011 1993

41°17'29.20" N 90°19'54.02" W elev 762 ft

Eye alt 2791 ft

SCHEDULE OF QUANTITIES		
ITS FIBER (WOODHULL TO MOLINE) - SHEET 28		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1598.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1598.0

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
c:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (1-95) - Final 4-30-12.dgn	DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/1/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM WOODHULL TO MOLINE) CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	31
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 28 OF 62 SHEETS STA. TO STA.