



UNDRGRD C MD  
399 FT. (PUSHED)  
ALONG ROUGH TERRAIN

COMMUNICATIONS VAULT  
1.0 EACH

UNDRGRD C MD  
644 FT.

UNDRGRD C MD  
514 FT. (PUSHED)  
UNDER ROADWAY AND  
ALONG ROUGH TERRAIN

I-74

A COMBINATION OF PUSHED AND TRENCHED CONDUIT WILL BE REQUIRED IN THIS AREA OF ROUGH TERRAIN. THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS PRIOR TO BIDDING.

SCHEDULE OF QUANTITIES		
ITS FIBER (WOODHULL TO MOLINE) - SHEET 36		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1557.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1607.0
COMMUNICATIONS VAULT	EACH	1.0

© 2011 Google

N. 1200TH AVE.

Imagery Date: 9/12/2011 1994

41°19'29.37" N 90°20'04.06" W elev 761 ft

Eye alt 2791 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>FIBER OPTIC CONDUIT AND CABLE PROJECT I-74 (FROM WOODHULL TO MOLINE) CONTINUED</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (1-95) - Final 4-30-12.dgn	DRAWN -	REVISED -			VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	39	
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -			CONTRACT NO. 68B04					
	PLOT DATE = 5/1/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. 36 OF 62 SHEETS	STA.	TO STA.			