



SCHEDULE OF QUANTITIES		
ITS FIBER (I-74/I-280 INTERCHANGE TO MOLINE) - SHEET 1		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	2357.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	2407.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 9/12/2011 1994

41°26'20.21" N 90°19'55.58" W elev 695 ft

Eye alt 2791 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
c:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (1-95) - Final 4-30-12.dgn	DRAWN -	REVISED -
	PLOT SCALE = 171.6216 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/1/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 / I-280 (FROM I-74 / I-80 INTERCHANGE TO MOLINE)

SCALE: SHEET NO. 1 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	66
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				