



UNDRGRD C MD
853 FT.

COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
611 FT. (PUSHED)
ROUGH TERRAIN

UNDRGRD C MD
626 FT.

A COMBINATION OF PUSHED AND TRENCHED CONDUIT WILL BE REQUIRED IN THIS AREA OF ROUGH TERRAIN. THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS PRIOR TO BIDDING.

SCHEDULE OF QUANTITIES		
ITS FIBER (I-74/I-280 INTERCHANGE TO MOLINE) - SHEET 6		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	2090.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	2140.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 9/12/2011 1994

41°26'53.40" N 90°22'07.81" W elev 662 ft

Eye alt 2791 ft

FILE NAME =	USER NAME = keathbr	DESIGNED -	REVISED -
c:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (I-95) - Final 4-30-12.dgn	DRAWN -	REVISED -
	PLOT SCALE = 171.6216' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/1/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 /I-280 (FROM I-74 /I-80 INTERCHANGE TO MOLINE) CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	71
CONTRACT NO. 68B04				
ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 6 OF 21 SHEETS STA. TO STA.

Google earth