GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

* BDE Form 2289 (Environmental Survey Request)

* A location map showing the size limits and location of the use area

* Signed property owner agreement form-D4 P10100

* Color photographs depicting the use area

* Borrow Area Entry Agreement form-D4 P10101

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS PROJECT.

JOB SPECIFIC NOTES

DUE TO THE DETERIORATION OF THE CONCRETE DECK BEAMS THE CONTRACTOR SHALL NOT STORE OR PARK ANY MATERIALS OR VEHICLES IN THE WB LANE DURING CONSTRUCTION FOR ANY PERIOD OF TIME.

FILE NAME =	USER NAME = ghidinaam	DESIGNED -	REVISED -					
emergencybeamreplacement.dgn		DRAWN -	REVISED -	STATE OF ILLINOIS	GE GE	GENERAL NOTES &		;&(
	PLOT SCALE = 40.0000 // 10.	CHECKED -	REVISED ~	DEPARTMENT OF TRANSPORTATION				
Default	PLOT DATE = 4/20/2012	DATE -	REVISED -	-	SCALE:	SHEET	OF	SHEETS

	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
COMMITMENTS	643	(11B)1-1	STARK	9	2			
			CONTRACT	NÔ. 6	8806			
TS STA. TO STA.	ILLINOIS FED. AID PROJECT							