

LOCATION OF WORK: FAI 74
RURAL INTERSTATE
REST AREA REPAIR
AT SALT KETTLE REST AREA
VERMILION COUNTY
FUNDING BREAKOUT: 100% STATE
CONSTRUCTION TYPE CODE: 0021

LOCATION OF WORK: FAI 74
RURAL INTERSTATE
REST AREA REPAIR
AT SALT KETTLE REST AREA
VERMILION COUNTY
FUNDING BREAKOUT: 100% STATE
CONSTRUCTION TYPE CODE: 0021

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
*X0327464	DRINKING FOUNTAIN REMOVAL AND REPLACEMENT	EACH	2.0
20200100	EARTH EXCAVATION	CU YD	240.0
20800150	TRENCH BACKFILL	CU YD	35.0
25000110	SEEDING, CLASS 1A	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25.0
25100115	MULCH, METHOD 2	ACRE	0.25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25.0
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,065.0
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	180.0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4,685.0
42400800	DETECTABLE WARNINGS	SQ FT	60.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	425.0

* DENOTES SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
44000600	SIDEWALK REMOVAL	SQ FT	4,685.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	180.0
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	1,000.0
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	25.0
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	405.0
44201299	DOWEL BARS 1 1/2"	EACH	2,865.0
44213100	PAVEMENT FABRIC	SQ YD	430.0
44213198	TIE BARS 1/2"	EACH	545.0
44213200	SAW CUTS	FOOT	7,160.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	25.0
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	290.0
54248510	CONCRETE COLLAR	CU YD	0.5
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	100.0
55100500	STORM SEWER REMOVAL 12"	FOOT	100.0

* DENOTES SPECIALTY ITEM