

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI 39

FAI 39

URBAN

RURAL

INTERSTATE

INTERSTATE

MCLEAN COUNTY

MCLEAN COUNTY

STA 41+92.0 TO 198+61.67

STA 198+61.67 TO 557+87.88

FUNDING BREAKOUT:

100% STATE

100% STATE

CONSTRUCTION TYPE CODE:

0005

0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
42001200	PAVEMENT FABRIC	SQ YD	100.0	70.0	30.0
44022029	PARTIAL DEPTH REMOVAL 3"	SQ YD	85.0	50.0	35.0
44200549	CLASS A PATCHES , TYPE I, 10 INCH	SQ YD	325.0	0.0	325.0
44200553	CLASS A PATCHES , TYPE II, 10 INCH	SQ YD	875.0	0.0	875.0
44200557	CLASS A PATCHES , TYPE III, 10 INCH	SQ YD	100.0	0.0	100.0
44200559	CLASS A PATCHES , TYPE IV, 10 INCH	SQ YD	275.0	0.0	275.0
44200982	CLASS B PATCHES , TYPE II, 11INCH	SQ YD	225.0	120.0	105.0
44200986	CLASS B PATCHES , TYPE III, 11 INCH	SQ YD	100.0	70.0	30.0
44201299	DOWEL BARS 11/2"	EACH	575.0	350.0	225.0
44213000	PATCHING REINFORCEMENT	SQ YD	1,575.0	0.0	1575.0
44213200	SAW CUTS	FOOT	12,950.0	1005.0	11945.0
44213204	TIE BARS 3/4"	EACH	575.0	0.0	575.0
67100100	MOBILIZATION	L SUM	1.0	0.3	0.7
70100420	TRAFFIC CONTROL AND PRTECTION, STANDARD 701411	EACH	13.0	8.0	5.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = bergana_j	DESIGNED - AJB	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\bergena_j\d0302063\0570973-sh.t-S00.dgn	DRAWN - AJB	REVISED -	39			D5 PATCHING 2013-1	MCLEAN	19	3	
PLOT SCALE = 40.0000' / 1" =	CHECKED -	REVISED -	SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. N/A TO STA. N/A			CONTRACT NO. 70973				
PLOT DATE = 3/22/2012	DATE - 3/12/2012	REVISED -	ILLINOIS FED. AID PROJECT							