

# SCHEDULE OF QUANTITIES

CLASS A PATCH 10" I 39 MAINLINE NORTHBOUND											
STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
			(FT)	(FT)	44200549 (SQ. YD.)	44200553 (SQ. YD.)	44200557 (SQ. YD.)	44200559 (SQ. YD.)	44213200 (FT)	44213204 (EACH)	44213000 (SQ. YD.)
236+72	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
239+81	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
241+00	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
242+96	I-39 MAINLINE (RURAL)	NBDL	8.0	6.0		5.3			48.0		5.3
246+71	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
249+00	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
249+18	I-39 MAINLINE (RURAL)	NBDL	8.0	6.0		5.3			48.0		5.3
253+50	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
256+00	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
256+20	I-39 MAINLINE (RURAL)	NBDL	30.0	6.0			20.0		114.0	30.0	20.0
256+88	I-39 MAINLINE (RURAL)	NBDL	10.0	12.0		13.3			78.0		13.3
256+55	I-39 MAINLINE (RURAL)	NBDL	30.0	6.0			20.0		114.0	30.0	20.0
258+15	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
262+00	I-39 MAINLINE (RURAL)	NBDL	40.0	6.0				26.7	144.0	40.0	26.7
263+40	I-39 MAINLINE (RURAL)	NBDL	15.0	6.0		10.0			69.0		10.0
264+60	I-39 MAINLINE (RURAL)	NBDL	20.0	12.0				26.7	108.0	20.0	26.7
269+20	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
270+45	I-39 MAINLINE (RURAL)	NBDL	8.0	6.0		5.3			48.0		5.3
272+50	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
274+00	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
274+40	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
274+60	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
274+80	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
275+30	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
275+36	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
275+40	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
277+86	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
277+96	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
279+10	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
281+40	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
281+80	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
282+46	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
282+70	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
282+83	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
283+30	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
283+60	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
284+97	I-39 MAINLINE (RURAL)	NBDL	8.0	12.0		10.7			72.0		10.7
285+71	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
286+42	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
287+18	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
287+38	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
287+45	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
287+60	I-39 MAINLINE (RURAL)	NBDL	6.0	6.0	4.0				42.0		4.0
289+05	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
297+42	I-39 MAINLINE (RURAL)	NBDL	6.0	12.0		8.0			66.0		8.0
NORTHBOUND SUBTOTALS OF CLASS A PATCH, 10 INCH					104.0	122.0	40.0	53.3	2529.0	120.0	319.3

**NOTE:**

PATCHING QUANTITIES IN ADDITION TO THOSE SHOWN IN THE SCHEDULES HAVE BEEN INCLUDED IN THE SUMMARY OF QUANTITIES, TO BE PLACED AT LOCATIONS DETERMINED BY THE ENGINEER.

FILE NAME =	USER NAME = bergana_j	DESIGNED - AJB	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pwork\pwork\berganaj\0302063\0570973-sht-schedule.dgn	DRAWN - AJB	REVISOR - _____				39	D5 PATCHING 2013-1	MCLEAN	19	11	
PLOT SCALE = 48.0000' / in.	CHECKED - _____	REVISOR - _____				CONTRACT NO. 70973					
PLOT DATE = 3/22/2012	DATE - 3/12/2012	REVISOR - _____				ILLINOIS FED. AID PROJECT					