

SCHEDULE OF QUANTITIES

CLASS A PATCH 10" I 39 MAINLINE SOUTHBOUND											
STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
			(FT)	(FT)	44200549 (SQ. YD.)	44200553 (SQ. YD.)	44200557 (SQ. YD.)	44200559 (SQ. YD.)	44213200 (FT)	44213204 (EACH)	44213000 (SQ. YD.)
236+25	I-39 MAINLINE (RURAL)	SBDL	10.0	6.0		6.7			54.0		6.7
237+50	I-39 MAINLINE (RURAL)	SBDL	10.0	6.0		6.7			54.0		6.7
237+60	I-39 MAINLINE (RURAL)	SBDL	15.0	6.0		10.0			69.0		10.0
239+35	I-39 MAINLINE (RURAL)	SBDL	25.0	6.0			16.7		99.0	25.0	16.7
239+40	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
239+50	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
241+00	I-39 MAINLINE (RURAL)	SBDL	15.0	6.0		10.0			69.0		10.0
242+70	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
243+50	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
246+90	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
247+00	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
248+50	I-39 MAINLINE (RURAL)	SBPL	40.0	6.0				26.7	144.0	40.0	26.7
253+00	I-39 MAINLINE (RURAL)	SBDL	15.0	6.0		10.0			69.0		10.0
254+50	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
258+13	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
260+00	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
278+50	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
279+00	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
280+15	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
282+60	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
284+75	I-39 MAINLINE (RURAL)	SBDL	30.0	6.0			20.0		114.0	30.0	20.0
285+00	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
286+00	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
289+00	I-39 MAINLINE (RURAL)	SBDL	8.0	6.0		5.3			48.0		5.3
290+00	I-39 MAINLINE (RURAL)	SBDL	15.0	6.0		10.0			69.0		10.0
302+06	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
312+60	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
317+65	I-39 MAINLINE (RURAL)	SBDL	70.0	6.0				46.7	234.0	70.0	46.7
318+50	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
325+50	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
327+15	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
331+15	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
334+90	I-39 MAINLINE (RURAL)	SBDL	8.0	6.0		5.3			48.0		5.3
336+50	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
338+16	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
343+86	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
346+81	I-39 MAINLINE (RURAL)	SBDL	20.0	12.0				26.7	108.0	20.0	26.7
350+50	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
351+25	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
352+16	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
352+94	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
353+42	I-39 MAINLINE (RURAL)	SBDL	8.0	6.0		5.3			48.0		5.3
354+16	I-39 MAINLINE (RURAL)	SBDL	15.0	6.0		10.0			69.0		10.0
355+17	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
356+74	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
SOUTHBOUND SUBTOTALS OF CLASS A PATCH, 10 INCH					48.0	271.0	36.7	100.0	3120.0	265.0	456.0

NOTE:

PATCHING QUANTITIES IN ADDITION TO THOSE SHOWN IN THE SCHEDULES HAVE BEEN INCLUDED IN THE SUMMARY OF QUANTITIES, TO BE PLACED AT LOCATIONS DETERMINED BY THE ENGINEER.

FILE NAME =	USER NAME = bergana_j	DESIGNED -	AJB	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	AJB	REVISED -						39	D5 PATCHING 2013-1	MCLEAN	19	13
		PLOT SCALE =	40.0000' / in.	CHECKED -			SCALE: N/A	SHEET NO. 3 OF 7 SHEETS	STA. N/A	TO STA. N/A	CONTRACT NO. 70973			
		PLOT DATE =	3/22/2012	DATE -		3/12/2012					ILLINOIS FED. AID PROJECT			