

# SCHEDULE OF QUANTITIES

CLASS A PATCH, 10" TOTALS		TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
		44200549	44200553	44200557	44200559	44213200	44213204	44213000
		(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(FT)	(EACH)	(SQ. YD.)
NORTHBOUND	RURAL	196.0	276.7	56.7	80.0	4812.0	165.0	609.3
*NB ADDITIONAL QUANTITY	RURAL	0.0	82.7	0.0	0.0	648.0	0.0	82.7
SOUTHBOUND	RURAL	108.0	383.0	36.7	173.3	4860.0	395.0	701.3
*SB ADDITIONAL QUANTITY	RURAL	0.0	117.3	0.0	0.0	930.0	0.0	117.3
TOTAL		304.0	859.7	93.3	253.3	11250.0	560.0	1510.7
ROUNDED TOTALS		325.0	875.0	100.0	275.0	11300.0	575.0	1575.0

\*ADDITIONAL QUANTITY NOT SHOWN IN SCHEDULE SHALL BE ADDED BY ENGINEER'S JUDGEMENT

CLASS B PATCH, 11" TOTALS		TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	DOWEL BARS	PAVEMENT FABRIC
		44200978	44200982	44200986	44200988	44213200	44213204	44201299	42001200
		(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(FT)	(EACH)	(EACH)	(SQ. YD.)
NORTHBOUND	URBAN	0.0	29.3	20.0	0.0	255.0	0.0	80.0	20.0
	RURAL	0.0	16.0	0.0	0.0	108.0	0.0	40.0	0.0
	TOTAL	0.0	45.3	20.0	0.0	363.0	0.0	120.0	20.0
SOUTHBOUND	URBAN	0.0	88.0	36.0	0.0	747.0	0.0	260.0	36.0
	RURAL	0.0	74.7	20.0	0.0	537.0	0.0	180.0	20.0
	TOTAL	0.0	162.7	56.0	0.0	1284.0	0.0	440.0	56.0
URBAN TOTAL		0.0	117.3	56.0	0.0	1002.0	0.0	340.0	56.0
RURAL TOTAL		0.0	90.7	20.0	0.0	645.0	0.0	220.0	20.0
FINAL TOTAL		0.0	208.0	76.0	0.0	1647.0	0.0	560.0	76.0
ROUNDED TOTALS		0.0	225.0	100.0	0.0	1650.0	0.0	575.0	100.0

PARTIAL DEPTH PATCHING TOTALS		PARTIAL DEPTH REMOVAL 3"	PARTIAL DEPTH PATCHING
		44022029	X4421000
		(SQ YD)	(TON)
NORTHBOUND	URBAN	8.1	1.5
	RURAL	8.1	1.5
	TOTAL	16.2	3.0
SOUTHBOUND	URBAN	37.8	7.0
	RURAL	24.3	4.5
	TOTAL	62.1	11.5
URBAN TOTAL		45.9	8.5
RURAL TOTAL		32.4	6.0
FINAL TOTAL		78.3	14.5
ROUNDED TOTALS		85.0	15.0

**NOTE:**

PATCHING QUANTITIES IN ADDITION TO THOSE SHOWN IN THE SCHEDULES HAVE BEEN INCLUDED IN THE SUMMARY OF QUANTITIES, TO BE PLACED AT LOCATIONS DETERMINED BY THE ENGINEER.