

PAVEMENT MARKING SCHEDULE

STATION	LENGTH	8" WHITE SOLID	4" WHITE SKIP DASH 10'-30'	4" YELLOW SOLID	4" WHITE SOLID	RRPM	RRPM REMOVAL	SHORT TERM PAVEMENT MARKING	TEMP PAVEMENT MARKING 4"	TEMP PAVEMENT MARKING 8"	WORK ZONE PAVE. MARK REMOVAL
RT (NB)		FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT	SQ. FOOT
1874+15.00 TO 1886+04.77	1190	0	297	1190	1190	30	30	122	2677	0	933
1887+74.10 TO 1904+53.30	1679	0	420	1679	1679	42	42	172	3778	0	1317
1905+94.33 TO 1915+93.22	999	0	250	999	999	24	24	103	2248	0	783
1917+60.71 TO 1921+00.00	339	0	85	339	0	8	8	21	424	0	148
1921+00.00 TO 1922+50.00	150	150	38	150	0	10	10	20	188	150	169
1922+50.00 TO 1934+50.00	1200	0	300	1200	1200	30	30	123	2700	0	941
1934+50.00 TO 1941+00.00	650	0	163	650	0	16	16	41	813	0	284
1941+00.00 TO 2007+34.30	6634	0	1659	6634	6634	166	166	682	14927	0	5203
2020+18.00 TO 2092+69.62	7252	0	1813	7252	7252	182	182	745	16316	0	5678
2094+95.50 TO 2437+19.69	34224	0	8556	34224	34224	856	856	3516	77004	0	26840
2437+19.59 TO 2486+20.00	4900	0	1225	4900	4900	122	122	503	11026	0	3843
2486+20.00 TO 2491+57.31	537	0	134	537	0	14	14	34	672	0	235
2490+44.72 TO 2492+00.00	155	155	39	155	0	10	10	20	194	155	175
2492+00.00 TO 2515+00.00	2300	0	575	2300	2300	58	58	236	5175	0	1804
2515+00.00 TO 2524+75.00	975	0	244	975	0	24	24	61	1219	0	427
2524+75.00 TO 2654+81.28	13006	0	3252	13006	13006	326	326	1336	29264	0	10200
2656+41.78 TO 2753+09.11	9667	0	2417	9667	9667	242	242	993	21751	0	7582
2754+89.11 TO 2862+79.00	10790	0	2697	10790	10790	270	270	1108	24277	0	8462
LT (SB)											
1874+15.00 TO 1886+04.77	1190	0	297	1190	1190	30	30	122	2677	0	933
1887+74.10 TO 1904+53.30	1679	0	420	1679	1679	42	42	172	3778	0	1317
1905+94.33 TO 1915+93.22	999	0	250	999	999	24	24	103	2248	0	783
1917+60.71 TO 1921+00.00	389	0	97	389	0	10	10	24	487	0	170
1921+00.00 TO 1922+50.00	1100	0	275	1100	1100	28	28	113	2475	0	863
1932+50.00 TO 1934+20.00	170	170	43	170	0	10	10	11	213	170	188
1934+20.00 TO 1939+62.53	543	0	136	543	0	26	26	22	678	0	233
1939+62.53 TO 2007+34.30	6772	0	1693	6772	6772	170	170	696	15236	0	5311
2020+18.00 TO 2092+69.62	7252	0	1813	7252	7252	182	182	745	16316	0	5687
2094+95.50 TO 2479+20.00	38425	0	9606	38425	38425	960	960	3947	86455	0	30134
2479+20.00 TO 2489+00.00	980	0	245	980	0	24	24	61	1225	0	429
2489+00.00 TO 2512+00.00	2300	0	575	2300	2300	58	58	236	5175	0	1804
2512+00.00 TO 2513+50.00	150	150	38	150	0	10	10	20	188	150	169
2513+50.00 TO 2518+75.00	525	0	131	525	0	14	14	33	656	0	230
2518+75.00 TO 2655+30.50	13656	0	3414	13656	13656	342	342	1403	30725	0	10709
2556+91.00 TO 2752+74.89	9584	0	2396	9584	9584	240	240	985	21564	0	7516
2754+54.89 TO 2862+79.00	10824	0	2706	10824	10824	270	270	1112	24354	0	8489
TOTALS		625	48296	193185	187621	4870	4870	19642	429102	625	149998
				380806							

FILE NAME =	USER NAME = ch1ds1	DESIGNED - GEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pwwork\pwwid\ch1ds1\d8301187\d876f90-	tr-pl.en.dgn	DRAWN - LAC	REVISED -			57	61-(2,3,3-1,4,5,5-1,6) RS-2	MARION	8	6	
PLOT SCALE = 100.0000' / in.		CHECKED - MDP	REVISED -			CONTRACT NO. 76F90					
PLOT DATE = 3/22/2012		DATE - 3/20/2012	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.				