

SCHEDULE OF QUANTITIES

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
206	04-00094-02-RS	MERCER	18	3
STA. 5+56 TO STA. 121+40.01				
FED. ROAD DIST. NO. 7		ILLINOIS		

ITEM NO.	DESCRIPTION	UNIT
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON
	STA. 5+56.00 (BUTT JOINT)	147
	LT. STA. 9+33.00 (SIDE ROAD)	147
	STA. 121+40.01 (BUTT JOINT)	85
	TOTAL	378
35800200	AGGREGATE BASE REPAIR	TON
	STA. 5+56.00 - 121+40.01 (ESTIMATED QUANTITY)	50
	TOTAL	50
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON
	F.E. RT. STA. 25+10	12.6
	F.E. RT. STA. 27+02	12.6
	F.E. RT. STA. 29+57	12.6
	F.E. LT. STA. 36+95	12.6
	F.E. LT. STA. 38+54	12.6
	F.E. RT. STA. 50+69	12.6
	F.E. LT. STA. 74+79	12.6
	F.E. RT. STA. 74+85	12.6
	F.E. LT. STA. 82+04	12.6
	F.E. RT. STA. 101+23	12.6
	F.E. LT. STA. 117+87	12.6
	F.E. RT. STA. 117+92	12.6
	TOTAL	151.2
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL
	STA. 5+56.00 - 121+40.01 (AGG BASE COURSE)	11,380
	STA. 5+56.00 - 121+40.01 (HMA BINDER COURSE)	1,423
	INCIDENTAL HMA	715
	TOTAL	13,518
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON
	STA. 5+56.00 - 121+40.01 (ESTIMATED QUANTITY)	100
	TOTAL	100
40600990	TEMPORARY RAMP	SQ YD
	STA. 5+56.00	50
	LT. STA. 9+33.00	50
	STA. 121+40.01	50
	TOTAL	150

ITEM NO.	DESCRIPTION	UNIT
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON
	STA. 5+56.00 - 121+40.01	5,242
	TOTAL	5,242
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON
	STA. 5+56.00 - 121+40.01	3,622
	TOTAL	3,622
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON
	S.R. LT. STA. 9+70	20.2
	P.E. RT. STA. 24+76	11.5
	P.E. RT. STA. 34+26	11.5
	P.E. RT. STA. 35+33	13.4
	P.E. RT. STA. 37+65	11.5
	P.E. RT. STA. 37+93	11.5
	P.E. LT. STA. 40+58	13.4
	P.E. RT. STA. 41+59	11.5
	P.E. LT. STA. 45+57	13.0
	C.E. RT. STA. 46+90	20.3
	P.E. LT. STA. 50+26	16.4
	P.E. RT. STA. 55+01	16.4
	P.E. RT. STA. 57+61	13.4
	P.E. RT. STA. 59+31	17.4
	P.E. LT. STA. 60+57	13.4
	P.E. RT. STA. 60+57	11.5
	P.E. LT. STA. 63+09	11.5
	P.E. RT. STA. 63+96	13.0
	P.E. LT. STA. 68+14	13.4
	P.E. RT. STA. 69+26	11.5
	P.E. RT. STA. 77+06	11.5
	P.E. RT. STA. 82+31	11.5
	P.E. RT. STA. 84+36	17.4
	P.E. LT. STA. 89+79	17.4
	P.E. LT. STA. 94+02	17.4
	P.E. LT. STA. 105+43	13.0
	P.E. LT. STA. 114+96	11.5
	MAILBOX TURNOUTS (21 TOTAL)	155.2
	TOTAL	530.3
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON
	LT. & RT. STA. 5+56.00 - 121+40.01	3,562
	TOTAL	3,562
	NOTE: DOESN'T INCLUDE SHOULDER AREA WITHIN F.E. WHICH IS INCLUDED IN AGGREGATE SURFACE COURSE, TYPE B	

ITEM NO.	DESCRIPTION	UNIT
67100100	MOBILIZATION	L. SUM
	COMPLETE	1
	TOTAL	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT
	SKIP-DASHED YELLOW (4' DASH, 40' SKIP)	
	CL STA. 5+56.00 - 121+40.01 (BINDER)	1,158
	CL STA. 5+56.00 - 121+40.01 (SURFACE)	1,158
	TOTAL	2,317
78001110	PAINT PAVEMENT MARKING LINE 4"	FOOT
	SOLID YELLOW	
	CL STA. 5+56 - 103+50 DOUBLE YELLOW (NO PASSING)	19,588
	CL STA. 103+50 - 121+40.01 LEFT LANE (NO PASSING)	1,790
	CL STA. 121+40.01 - 122+40.03 DOUBLE YELLOW (BRIDGE)	200
	SKIP-DASHED YELLOW (10' DASH, 30' SKIP)	
	CL STA. 103+50 - 121+40.01 RIGHT LANE	448
	SOLID WHITE (EDGE LINE)	
	LT AND RT. STA. 5+56 - 121+40.01	23,168
	TOTAL	45,194
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L. SUM
	COMPLETE	1
	TOTAL	1
Z0034105	MATERIAL TRANSFER DEVICE	TON
	STA. 5+56.00 - 121+40.01 (BINDER)	5,242
	STA. 5+56.00 - 121+40.01 (SURFACE)	3,622
	TOTAL	8,863