

PROPOSED STORM SEWER & REMOVAL - CONTINUED

LOCATION	INLETS, TYPE A			INLETS, TYPE B		INLETS, SPECIAL			JUNCTION BOX	TRENCH DRAIN				SPECIAL GRATE NO. 1	MANHOLES, TYPE A, 5' DIA.	MANHOLES, TYPE A, 6' DIA.	MANHOLES, 9' DIA.	PRECAST CONCRETE BOX CULVERT
	TYPE 1 FRAME, CLOSED LID	SPECIAL FRAME AND GRATE, SPECIAL	TYPE 3V FRAME AND GRATE	TYPE 3V FRAME AND GRATE	SPECIAL FRAME AND GRATE	NO. 1	NO. 2	NO. 3		NO. 1*	NO. 2*	NO. 3*	NO. 4*					
LT/RT STATION TO STATION	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	L SUM	FOOT*	FOOT*	FOOT*	FOOT*	EACH	EACH	EACH	EACH	FOOT
MOORE STREET																		
LT 101+91.55 TO 102+25.00		2									10				1			
AR 102+04.90 TO 102+04.90																		
RT 101+20.95 TO 102+04.90			1								10				1			
RT 102+04.99 TO 103+81.13			3															
RT 102+72.70 TO 102+72.70																		
LT 103+22.20 TO 103+22.20																		
LT 103+25.00 TO 103+81.12			1	1														
AR 103+82.20 TO 103+82.20																		
LT 103+82.20 TO 105+73.50																		
AR 103+81.13 TO 103+81.13		1																
RT 103+81.13 TO 104+24.26															1			
RT 104+24.26 TO 107+55.59			4			1					10				1			
AR 105+34.78 TO 105+34.78			1															
RT 105+43.00 TO 105+43.00																		
RT 105+87.00 TO 107+83.00																		
AR 107+54.70 TO 107+91.00																		
LT 107+91.00 TO 110+95.00																		
RT 107+83.00 TO 111+29.00																		
LT 111+10.78 TO 111+10.78																		
AR 106+25.00 TO 106+25.00			1															
AR 106+92.00 TO 106+92.00			1															
AR 107+44.21 TO 107+44.21			1															
RT 107+55.59 TO 108+35.74	1						2						4					77.2
RT 108+35.74 TO 111+28.29		1	4	2	1				1			32				1		
AR 108+55.00 TO 108+55.00		1																
AR 109+50.00 TO 109+50.00			1															
AR 110+39.52 TO 110+39.52			1															
AR 110+83.93 TO 110+83.93															1			
LT 110+66.72 TO 111+10.78			2	1														
FOURTH STREET																		
RT 1000+15.00 TO 1001+08.00						3		2										
LT 1000+15.00 TO 1000+75.44						2		2										
RT 1000+19.00 TO 1001+08.00																		
THIRD STREET																		
RT 107+49.71 TO 2000+03.56	2					3							10					80.9
LT 1001+08.00 TO 2000+88.25	1					4							10					75.8
RT 2000+16.80 TO 2001+03.70																		
TOTALS	4	5	21	4	1	13	2	4	1	10	10	10	32	24	1	4	1	233.9
USE	4	5	21	4	1	13	2	4	1	10	10	10	32	24	1	4	1	233.9

*INFORMATION ONLY. THE TOTAL PAY QUANTITY FOR "TRENCH DRAIN" IS 4 EACH

HMG ENGINEERS, INC., 1075 LAKE ROAD, PO BOX 70, CARLYLE, IL 62231 PHONE (618) 594-3711 WWW.HMGENGINEERS.COM

FILE NAME :	USER NAME : USERDESCR.	DESIGNED - HMG: CRW & EDW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
H:\SIBBWater-loc\locres\Pres\IV\CADD\PCD	HAY\SIBB\res\resd\resd.dgn	DRAWN - HMG: CRW, EDW, & KOJ	REVISED -		9375	06-00032-03-PV	MONROE	93	10
PLOT SCALE : 1/8"=1'-0"		CHECKED - HMG: CRW	REVISED -		CONTRACT NO. 97488				
PLOT DATE : 3/28/2012		DATE -	REVISED -		FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.