RO020 Total Sheets: 70

INDEX TO SHEETS

GENERAL

- COVER SHEET / INDEX TO SHEETS (CVR1)
- SUMMARY OF QUANTITIES (QTY1)
- SITE PLAN AND CONTROL (SPL1)
- PHASING PLAN SUMMARY (PPM1)
- PHASING PLAN NOTES (PPN1)
- PHASING PLAN DETAILS (PPD1)
- ONSITE BORROW / MILLING STOCKPILE (OBM1)
- STORMWATER POLLUTION PREVENTION PLAN (SWP1)
- STORMWATER POLLUTION PREVENTION NOTES (SWN1)
- STORMWATER POLLUTION PREVENTION DETAILS (SWD1)

REHABILITATE RWY 1/19

- TYPICAL SECTION 1/19 (TYP1)
- TYPICAL SECTION TXY D 1 (TYP2)
- TYPICAL SECTION TXY D 2 (TYP3) 13
- EXISTING CONDITIONS AND REMOVALS (EXC1-2)
- 16-17 RUNWAY 1/19 PLAN / PROFILE (RPP1-2)
- TAXIWAY D PLAN/PROFILE (DPP1)
- RUNWAY 1/19 GRADING PLAN (RGP1) 19
- 20 TAXIWAY D GRADING PLAN (DGP1)
- JOINTING PLAN (JTP1-2) 21-22
- 23 JOINTING DETAILS (JTD1)
- ELECTRICAL AND MARKING PLAN (EMP1-2) 24-25
- 26. HOMERUN PLAN (HRP1)
- GROOVING PLAN AND DETAILS (GPD1)
- ENGINEERING INFORMATION (ENG1)

CONSTRUCT TXY F SHOULDERS AND WIDEN TXY M AND K

- GENERAL NOTES AND LEGENDS TXY'S F, K & M (GNL1)
- TYPICAL SECTIONS TXY'S F. K & M (TYP4) 30
- EXISTING CONDITIONS AND REMOVALS TXY'S F, K & M 1 (EXC3-5)
- PAVING AND DRAINAGE PLAN TXY'S F, K & M 1 (PDP1-3) 34-36
- 37-39 GRADING PLAN TXY'S F, K & M - 1 (GDP1-3)
- LIGHTING AND MARKING PLAN TXY'S F, K & M 1 (LMP1-2) 40-41
- 42-43 ELECTRICAL PLAN TXY'S F. K & M - 1 (ELP1-2)
- INDEX TO CROSS SECTIONS TXY'S F, K, M (INX1)
- CROSS SECTIONS TXY'S F, K, & M (XSC1-4)

DETAILS

- 49 DRAINAGE AND UNDERDRAIN DETAILS (SSD1)
- STORM SEWER INLET ADJUSTMENT DETAIL (SSD2)
- STORM SEWER MANHOLE ADJUSTMENT DETAIL (SSD3)
- SANITARY SEWER MANHOLE ADJUSTMENT DETAIL (SND1) 52
- ELECTRICAL DETAILS (ELD1-6)
- MARKING DETAILS (MRD1-3) 59-61

ADD ALT # 1 AND #2

- SITE PLAN AND CONTROL (ASP1) 62
- TYPICAL SECTION (ATY1)
- EXISTING CONDITIONS AND REMOVALS (AEX1)
- RUNWAY 1/19 PLAN AND PROFILE ADD ALT #1 (APP1)
- RUNWAY 1/19 PLAN AND PROFILE ADD ALT #2 (APP2)
- RUNWAY 1/19 GRADING PLAN (AGP1)
- JOINTING PLAN (AJT1)
- ELECTRICAL / MARKING AND LANDSCAPING (AEM1)
- GROOVING PLAN (AGP1)

GREATER ROCKFORD AIRPORT AUTHORITY ROCKFORD, ILLINOIS


CONSTRUCTION PLANS FOR CHICAGO ROCKFORD INTERNATIONAL AIRPORT

REHABILITATE RUNWAY 1/19 PHASE 2


FINAL SUBMITTAL

ILLINOIS PROJECT: RFD-4183 A.I.P. PROJECT: 3-17-0088-XX

> **APRIL 20, 2012** (JUNE 15, 2012 LETTING)



LOCATION MAP



LICENSED





MIKE DUNN

DIRECTOR

DESIGN INFORMATION

RANGE 1 EAST

Rockford, Illinois


DATE -

ROCKFORD TOWNSHIP

ALP DATA: APPROACH CAT. / DESIGN GROUP: D5 DESIGN AIRCRAFT: 747-400

(MAXIMUM EQUIPMENT HEIGHT = 25')







SUBMITTED B Travis A. Strait, P.E.

4/20117

license expires 11-30-2013

11258-03-00/06


SITE PLAN


PROJECT

LOCATION

GREATER ROCKFORD

6 **SUMMARY OF QUANTITIES RO020** ADDITIVE ALTERNATE #1 -ADDITIVE ALTERNATE #2 -BASE BID - RUNWAY 1/19 BASE BID - CONSTRUCT **ADDITIONAL RUNWAY 1/19** ADDITIONAL RUNWAY 1/19 REHABILITATION (PHASE 2) TAXIWAY F SHOULDERS REHABILITATION REHABILITATION DESCRIPTION QUANTITY RECORD OLIANTITY OLIANTITY RECORD OLIANTITY RECORD (F/S/L) QUANTITY (F/S/L) (F/S/L) QUANTITY (F/S/L) QUANTITY 1/C #8 5 KV UG CABLE 10,260.00 4,155.00 1,610.00 1,620.00 CHICAGO ROCKFORD 1/C #8 5 KV UG CABLE IN UD 650.00 6,140.00 INTERNATIONAL AIRPORT 1-WAY CONC. ENCASED DUCT 400.00 2,900.00 G 4 AR110550 SPLIT DUCT 120.00 AR110554 **EXTEND 4-WAY DUCT** 160.00 MIKE DUNN AR110610 **ELECTRICAL HANDHOLE** EACH 4.00 DIRECTOR REMOVE ELECTRICAL HANDHOLE AR110906 EACH 6.00 MITL-BASE MOUNTED EACH AR125415 EACH AR125525 HIRL, INPAVEMENT 2.00 EACH 10 AR125565 SPLICE CAN 2.00 AR125902 REMOVE BASE MOUNTED LIGHT EACH 2.00 AR125916 RELOCATE RGL EACH 3.00 ADJUST BASE MOUNTED LIGHT AR125942 EACH 26.00 CRAWFORD, MURPHY & TILLY, INC. ADJUST INPAVEMENT LIGHT FACH 14 AR125943 40.00 5.00 ADJUST SPLICE CAN EACH 15 AR125946 2.00 1.00 RELOCATE BASE MOUNTED LIGHT 16 FACH 35.00 AR125962 2 00 AR125963 RELOCATE INPAVEMENT LIGHT FACH 1.00 AR125964 RELOCATE TAXI GUIDANCE SIGN EACH 2.00 11.00 ENGINEER'S FIELD OFFICE AR150510 1.00 FIELD LABORATORY LS 20 AR150515 1.00 AR150520 MOBILIZATION LS Chicago Rockford UNCLASSIFIED EXCAVATION CY 5.468.00 1,000.00 22 AR152410 23 AR152441 ON-SITE BORROW CY 4.500.00 International Airport SOIL STABILIZATION FABRIC AR152540 SY 13,180.00 Rockford, Illinois AR156510 SILT FENCE 3,650.00 1,000.00 AR156512 BALES EACH 56.00 72.00 AR208515 POROUS GRANULAR EMBANKMENT CY 100.00 Ε AR209608 CRUSHED AGG. BASE COURSE - 8" SY 9,475.00 1,200.00 AR209612 CRUSHED AGG. BASE COURSE - 12" SY 3,705.00 Greater Rockford AR401610 BITUMINOUS SURFACE COURSE TON 2,445.00 455.00 200.00 5,170.00 Airport Authority BITUMINOUS SURFACE TEST SECTION EACH BITUMINOUS PAVEMENT GROOVING SY 5,500.00 REMOVE BITUMINOUS PAVEMENT SY 1,425.00 770.00 270.00 4,300.00 REM & REPLACE BIT PAVEMENT - TYPE A SY REM & REPLACE BIT PAVEMENT - TYPE B SY 35 115.00 AIP Proj: 3-17-0088-XX BITUMINOUS BASE COURSE TON 350.00 2,750.00 65.00 473.00 D IL Proj: RFD-4183 BITUMINOUS BASE TEST SECTION EACH AR501520 20" PCC PAVEMENT SY 26,675.00 5,000.00 6,000.00 EACH AR501530 PCC TEST BATCH 23,200.00 AR501540 PCC PAVEMENT GROOVING SY 4,350.00 5,200.00 41 AR602510 BITUMINOUS PRIME COAT GAL 6,590.00 825.00 BITUMINOUS TACK COAT 4,650.00 42 AR603510 GAL 3,850.00 350.00 420.00 43 PAVEMENT MARKING - WATERBORNE 11,500.00 24.050.00 2.400.00 AR620520 1.980.00 APPROVED AS WORKING PLAN PAVEMENT MARKING - BLACK BORDER SF 2,040.00 AR620525 17,360.00 12.500.00 2,000.00 44 PAVEMENT MARKING REMOVAL 13.945.00 45 AR620900 18" RCP, CLASS IV AR701518 70.00 47 6" PERFORATED UNDERDRAIN LF 3,200.00 2,318.00 600.00 720.00 AR705506 UNDERDRAIN COLLECTION STRUCTURE AR705635 EACH 48 1.00 C AR705640 UNDERDRAIN CLEANOUT EACH 11.00 49 720.00 REMOVE UNDERDRAIN 3,200.00 2,389.00 600.00 AR705900 REMOVE UNDERDRAIN CLEANOUT EACH AR705904 5.00 REMOVE COLLECTION STRUCTURE FACH AR705905 1.00 53 AR751411 INLET - TYPE A EACH 3.00 AR751550 MANHOLE 5' EACH 2.00 DESCRIPTION REV DATE AR751900 REMOVE INLET **EACH** 3.00 PROJECT NAME AR751940 ADJUST INLET EACH 2.00 AR751943 ADJUST MANHOLE EACH REHABILITATE AR770905 REMOVE SANITARY MANHOLE EACH RUNWAY 1/19 AR770945 ADJUST SANITARY MANHOLE EACH AR800850 2 - 1/C #2 XLP-USE, 1/C #8 GND IN UD LF 1,700.00 PHASE 2 В AR800856 17" BITUMINOUS PAVEMENT MILLING SY 26,700.00 5,000.00 6,000.00 2" BITUMINOUS PAVEMENT MILLING SY 4,200.00 SHEET TITLE: AR800858 0-2" BITUMINOUS PAVEMENT MILLING SY 6,150.00 ADJUST PAVEMENT SENSOR EACH SUMMARY OF SEEDING ACRE 3.00 3.30 AR901510 0.49 1.27 **QUANTITIES** TOPSOILING SY 14,000.00 HEAVY-DUTY HYDRAULIC MULCH 3.30 ACRE 3.00 0.49 1.27 CMT-RFD CMT-RFD CMT-ARR PROJECT NO.: 11258-03-00/06 APRIL 20, 2012 **SUMMARY OF QUANTITIES** (QTY1) SHEET 2 OF 70 SHEETS





PHASING PLAN PROJECT NOTES:

5. GATE SECURITY:

THE GATE SHALL BE MAINTAINED, CLOSED AND LOCKED AS DIRECTED BY THE DEPUTY DIRECTOR OF OPERATIONS. SHOULD THE CONTRACTOR'S OPERATIONS REQUIRE THE GATE TO REMAIN OPEN TO PROVIDE ACCESS TO HAULING OPERATIONS, A COMPETENT GATE GUARD EMPLOYED BY THE CONTRACTOR SHALL BE REQUIRED TO CONTROL ACCESS TO THE AIRFIELD. A \$1,000 FINE SHALL BE ASSESSED FOR ANY OCCURRENCE OF AN UNSECURE GATE THAT IS THE CONTRACTOR'S RESPONSIBILITY. AN UNSECURED GATE SHALL BE DEFINED AS ANY GATE THAT IS NOT WITHIN THE SIGHT AND PHYSICAL CONTROL OF THE CONTRACTOR'S GUARD. IN THE EVENT THAT THE GATE MAY NOT BE SECURED. THE CONTRACTOR WILL BE CHARGED FOR AIRPORT PERSONNEL TO REMAIN AT THE GATE UNTIL SECURED.

6. CONSTRUCTION OUTSIDE OF BARRICADED AREAS REQUIRING TAXIWAY / **RUNWAY CLOSURES:**

WORK OUTSIDE THE BARRICADED LINES WITHIN THE AOA AREAS SHOWN SHALL REQUIRE TEMPORARY DAYTIME ONLY CLOSURES OF THE RUNWAY 7/25 AND TAXIWAY F. THIS WORK SHALL BE EXPEDITED AND PRIORITIZED TO MINIMIZE CLOSURE TIME OF THE ACTIVE PAVEMENTS. CONSTRUCTION ACTIVITIES WILL NOT BE PERMITTED WITHIN 250' OF CENTERLINE ON ALL ACTIVE RUNWAYS AND WITHIN 160' OF CENTERLINE ON ALL ACTIVE TAXIWAYS. IN ADDITION, THIS WORK WILL REQUIRE ALL CREWS TO SUPPLY AND HAVE IN THEIR POSSESSION AT ALL TIMES AT LEAST ONE AIRPORT RADIO TO COMMUNICATE DIRECTLY WITH THE ATCT (AIR TRAFFIC CONTROL TOWER). THE OPERATOR OF THE AIRPORT RADIO SHALL BE FAMILIAR WITH AIRPORT RADIO PROCEDURES AND BE TUNED INTO THE GROUND CONTROL FREQUENCY AT ALL TIMES.

7. UNAUTHORIZED ACCESS TO AIRFIELD:

THE CONTRACTOR SHALL RESTRICT ALL CONSTRUCTION ACTIVITIES TO THE CONSTRUCTION AREA DETAILED IN THE PHASING PLAN. ANY UNAUTHORIZED MOVEMENTS, PEDESTRIAN OR VEHICULAR, BEYOND THE CONSTRUCTION LIMITS SHOWN SHALL BE CONSIDERED AN AIRFIELD INCURSION. AIRFIELD INCURSIONS, AT THE DISCRETION OF THE AIRPORT DEPUTY DIRECTOR OF OPERATIONS, MAY BE FINED \$10,000.00 PER INCIDENT. INCURSION FINES WILL BE ASSESSED IMMEDIATELY AND DEDUCTED FROM MONIES DUE THE CONTRACTOR ON THE NEXT CONSTRUCTION PAYMENT.

PHASE	WORK AREA	ALLOWABLE WORK PERIODS	AIRPORT OPERATIONAL RESTRICTIONS	ANTICIPATED SCHEDULE
1 (EXPEDITED)	TAXIWAY M AND K WITHIN RUNWAY 7/25 SAFETY AREA	DAILY CLOSURES OF RUNWAY 7/25 WILL BE PERMITTED 7:00 A.M 7:00 P.M.	WORK WITHIN 250' OF RUNWAY 7/25 CENTERLINE WILL REQUIRE THE TEMPORARY CLOSURE OF RUNWAY 7/25. WORK REQUIRING ANY CLOSURE SHALL BE EXPEDITED AND PRIORITIZED TO MINIMIZE CLOSURE TIME. AT THE END OF EACH DAYS CONSTRUCTION ACTIVITIES THE RUNWAY SHALL BE REOPENED.	(14 CALENDAR DAYS)
2	TAXIWAY F BETWEEN STATION 137+50 TO 167+50 AND TAXIWAY M AND K OUTSIDE RUNWAY 7/25 SAFETY AREA	DAILY CLOSURES OF TAXIWAY F WILL BE PERMITTED 7:00 A.M 7:00 P.M.	WORK ON TAXIWAY F WILL REQUIRE THE TEMPORARY CLOSURE OF TAXIWAY F BETWEEN STATION 137+50 TO 167+50. WORK REQUIRING ANY CLOSURE SHALL BE EXPEDITED AND PRIORITIZED TO MINIMIZE CLOSURE TIME. AT THE END OF EACH DAYS CONSTRUCTION ACTIVITIES THE TAXIWAY SHALL BE REOPENED.	(32 CALENDAR DAYS)
3	RUNWAY 1/19 STATION 45+50 TO 71+50. IF AWARDED ADDITIVE ALTERNATE 1 AND 2 APPLICABLE AREAS	NO RESTRICTIONS	WORK ON RUNWAY 1/19 WILL REQUIRE THE CLOSURE OF RUNWAY 1/19 FOR THE DURATION OF THE CONSTRUCTION ACTIVITIES.	(60 CALENDAR DAYS)
				106 CALENDAR DAYS

IF ADD ALT #1 IS AWARDED, 8 ADDITIONAL CALENDAR DAYS WILL BE AWARDED TO PHASE 3 (TOTAL PROJECT CALENDAR DAYS = 114 DAYS).

IF ADD ALT #1 AND #2 ARE AWARDED, 18 ADDITIONAL CALENDAR DAYS WILL BE AWARDED TO PHASE 3 (TOTAL PROJECT CALENDAR DAYS = 124 DAYS)

1. SUGGESTED SEQUENCE OF CONSTRUCTION:

PHASING PLAN GENERAL NOTES:

THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE RESIDENT ENGINEER. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT DEPUTY DIRECTOR OF OPERATIONS.

2. STAGING AREA RESTORATION:

ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A STAGING AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DEPUTY DIRECTOR OF OPERATIONS. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE PAVEMENTS / AREAS SHALL BE INCIDENTAL TO THE CONTRACT.

3. HAUL ROUTE / HAUL ROUTE RESTORATION:

THE CONTRACTOR SHALL USE THE HAUL ROUTE(S) AS SHOWN IN THESE PLANS. THE COST OF MAINTAINING THE HAUL ROUTE(S) SHALL BE INCIDENTAL TO CONTRACT. ALL HAUL ROUTE(S) INCLUDING EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DEPUTY DIRECTOR OF OPERATIONS. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE HAUL ROUTE(S) SHALL BE INCIDENTAL TO CONTRACT.

4. AIRPORT APPROVAL OF PHASING:

THE RESIDENT ENGINEER AND AIRPORT DEPUTY DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT OPERATIONS. AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. VEHICULAR TRAFFIC AND CONTRACTOR ACTIVITIES SHALL YIELD TO AIRCRAFT OPERATIONS. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS, THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO THE OWNER.

5. AIRFIELD PAVEMENT / SITE DEBRIS REMOVAL:

THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING RUNWAYS AND TAXIWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS, THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS. THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO USE. FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE USED.

(NOTES CONTINUED ON PHASING PLAN DETAILS - PPD1)

PHASING PLAN NOTES (PPN1)

RO020

CHICAGO ROCKFORD INTERNATIONAL AIRPORT

MIKE DUNN DIRECTOR



CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS.

Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4183



REHABILITATE RUNWAY 1/19 PHASE 2

SHEET TITLE:

PHASING PLAN **NOTES**

CHECKED:

CMT-RFD CMT-RFD CMT-ARR 11258-03-00/06 PROJECT NO .: DATE: APRIL 20, 2012

SHEET 5 OF 70 SHEETS

SHEET NO. PPN1

C

Н

G

F

Ε

D

1. APPROVED PROGRESS SCHEDULE:

DAYS PRIOR TO START OF CONSTRUCTION.

BARRICADE/FENCING PERIMETERS SHOWN.

VEHICLES ENTERING AND LEAVING THE SITE.

DURING CONSTRUCTION.

2. NOTAM (NOTICE TO AIRMEN) COORDINATION:

COORDINATION WITH AIRPORT / FAA PERSONNEL.

3. CONSTRUCTION SITE ACCESS AND STAGING AREA:

PRIOR TO THE START OF CONSTRUCTION, AN APPROVED PROGRESS

OF ALL PHASES, INCLUDING ALL AOA WORK REQUIRING DAYTIME ONLY

CLOSURES OF TAXIWAYS AND RUNWAYS. THE APPROVED PROGRESS

SCHEDULE SHALL BE DISTRIBUTED TO ALL PARTIES AT LEAST 3 WORKING

THE RESIDENT ENGINEER SHALL COORDINATE NOTAM AND FAA FACILITY

THE CONTRACTOR ACCESS ROAD AND STAGING AREAS SHALL BE AS SHOWN

ON THE REFERENCED PLAN. THE CONTRACTOR SHALL MAINTAIN AND REPAIR

THE CONSTRUCTION ACCESS ROAD AND STAGING AREA TO ITS ORIGINAL

WORK AREA SHALL BE RESTRICTED FROM ACTIVE AOA AREAS WITH THE

THE ENTRANCES SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY

CONSTRUCTION VEHICLE ACCESS AND WILL ONLY BE ACCESSIBLE DURING

TO THE CITY OF ROCKFORD AND IDOT CONSTRUCTION STANDARDS FOR

THE CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE

4. CONSTRUCTION EQUIPMENT FLAGGING / BEACON REQUIREMENTS:

BEACON (FLASHING YELLOW) LIGHTS ON ALL EQUIPMENT AT ALL TIMES

THE CONTRACTOR'S SCHEDULED WORK DAY. ALL SIGNAGE SHALL CONFORM

STAGING AREAS AND ACCESS FOR THIS AREA WILL NOT BE ALLOWED. THIS

CONDITION AT NO ADDITIONAL COST TO THE CONTRACT. ALTERNATE

SCHEDULE SHALL BE EXECUTED BY THE CONTRACTOR AND MONITORED BY

THE RESIDENT ENGINEER. THIS SCHEDULE SHALL SHOW START/ STOP DATES

В

Α

PHASING PLAN GENERAL NOTES (CONT'D):

(NOTES CONTINUED ON PHASING PLAN NOTES - PPN1)

6. PROJECT LIGHTING OUTSIDE OF DAYLIGHT HOURS:

WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVEABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY.

7. EXISTING UTILITY COORDINATION:

Η

G

F

Ε

D

С

В

Α

COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. SEE SECTION 50-17 OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES. INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.

SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATIONS.

8. TRAFFIC CONTROL PAYMENT:

PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING. BUT NOT LIMITED TO, TEMPORARY CONSTRUCTION FENCING BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A.) LATH AND RIBBON, ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. LOW PROFILE BARRICADES WITH STEADY BURN RED LIGHTS SHALL BE PLACED ON 15' CENTERS. LOW PROFILE BARRICADES SHALL BE PLACED AS SHOWN ON THIS PLAN AND AS DIRECTED BY THE RESIDENT ENGINEER. WHEN NOT IN USE, THESE BARRICADES SHALL BE STORED AT THE CONTRACTOR'S STAGING AREA OR OFF SITE. ACCESS TO THE ACTIVE RUNWAY AND TAXIWAY PAVEMENTS (TOWER CONTROLLED AREAS) SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON THE CLOSEST BARRICADES (2 EACH, RIGHT AND LEFT) AT THE ENTRANCE. IN ADDITION TO THE STOP SIGNS, WARNING SIGNS (2 EACH, RIGHT AND LEFT) SHALL BE MOUNTED, WARNING SIGNS SHALL STATE "TOWER CONTROL AREA / UNAUTHORIZED ACCESS SUBJECT TO FINE." ALL NON AIRFIELD LOCATIONS REQUIRING BARRICADES SHALL BE TYPE II BARRICADES AND SHALL CONFORM TO IDOT STANDARD 702001. FOR AIRSIDE BARRICADE PLACEMENT, SEE PHASING PLAN SUMMARY SHEETS. FOR ROADWAY PROTECTION, SEE TEMPORARY TRAFFIC CONTROL PLAN AND GENERAL NOTES AND DETAILS SHEETS.

9. DRIVERS TRAINING AND BADGING:

DRIVER'S TRAINING AND BADGING SHALL BE REQUIRED FOR THE CONTRACTOR'S SUPERVISORY PERSONNEL, OTHER CONSTRUCTION PERSONNEL CAN BE WITHIN THE AIRFIELD LIMITS PROVIDED THAT THEY ARE UNDER ESCORT AND IN THE PRESENCE OF AN AUTHORIZED SUPERVISOR. THE DRIVER'S TRAINING AND BADGING OF THE INITIAL SUPERVISORY PERSONNEL MUST BE COMPLETED PRIOR TO THE START OF CONSTRUCTION.

10. DUST CONTROL REQUIREMENTS:

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE REQUIRED TO BE ON SITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE DEPUTY DIRECTOR OF OPERATIONS. PAYMENT FOR DUST CONTROL SHALL BE INCIDENTAL TO THE CONTRACT.

11. OPERATIONAL SAFETY ON AIRPORT DURING CONSTRUCTION (AC 150/5370-2F):

ALL WORK SHALL CONFORM TO AC 150/5370-2F OPERATIONAL SAFETY ON AIRPORT DURING CONSTRUCTION. THIS AC IS AVAILABLE AT www.faa.gov/arp/pdf/5370-2f.pdf.

12. STAGING AREA:

THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, SHALL BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES, EQUIPMENT REFUELING, EQUIPMENT MAINTENANCE AND EQUIPMENT TRANSFERS SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING AREA.

13. AIRFIELD LIGHTING COORDINATION:

THE CONTRACTOR SHALL BE REQUIRED TO ESTABLISH A COORDINATION PLAN WITH THE AIRPORT DEPUTY DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE, REGARDING DE-ENERGIZING AND ENERGIZING OF THE AIRFIELD LIGHTING CIRCUITS AT THE START AND END OF EACH CONSTRUCTION DAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT OWNED UTILITIES AND SHALL BE DONE SO AT NO EXTRA COST TO THE CONTRACT.


14. WEEKLY COORDINATION MEETINGS:

WEEKLY COORDINATION MEETINGS SHALL BE REQUIRED TO DISCUSS PROJECT PROGRESS. AS A MINIMUM, PROJECT SCHEDULE AND GATE VISITOR LOGS SHALL BE DISCUSSED. REPRESENTATION BY THE PRIME CONTRACTOR IS MANDATORY.

15. TEMPORARY CABLES:

ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER AND AIRPORT FOR ALL PHASES. ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO CONTRACT.

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SPECIAL PROVISIONS SECTION 30-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT: • REHABILITATE TAXIWAY J AND L




NOT TO SCALE


70,00

CLOSED RUNWAY MARKER DETAIL
ON PAVEMENT - NO SCALE

- 1. CLOSED RUNWAY MARKERS SHALL BE YELLOW.
- 2. MARKERS SHALL BE A MATERIAL APPROVED BY THE ENGINEER AND THE AIRPORT.
- 3. CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION.
- 4. MARKERS SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN.
- 5. COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

6. DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT AND TOWER PERSONNEL. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET OR AS DIRECTED BY THE ENGINEER AND AIRPORT. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION.





RO020

LOW PROFILE BARRICADES

ON PAVEMENT - NO SCAL

- 1 . LOW PROFILE BARRICADES SHALL BE PLACED 15' ON CENTER AT LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE RESIDENT ENGINEER. BARRICADES SHALL BE WEIGHTED WITH A MINIMUM OF 6 SAND BAGS TO PREVENT THEM FROM BEING BLOWN OVER.
- 2. LIGHTS SHALL BE BATTERY OPERATED. LENS SHALL BE RED AND BE ABLE TO ROTATE 90°.
- 3. FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- 4. ALTERNATE LENSES SO THAT EVERY OTHER LENS IS ROTATED $90\c C$
- 5. BARRICADES SHALL BE OF LOW MASS, EASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT'S COMPONENTS, AND WEIGHTED OR STURDILY ATTACHED TO THE SURFACE. IF AFFIXED TO THE SURFACE, THE BARRICADE MUST BE FRANGIBLE AT GRADE LEVEL OR AS LOW POSSIBLE, BUT NOT TO EXCEED 3 INCHES ABOVE THE GROUND.
- 6. ALL COST ASSOCIATED WITH THE LOW PROFILE BARRICADES SHALE BE CONSIDERED INCIDENTAL TO THE CONTRACT.

PHASING PLAN DETAILS (PPD1)

H RFD

CHICAGO ROCKFORD
INTERNATIONAL AIRPORT

MIKE DUNN DIRECTOR



CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS

Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4183

APPROVED AS WORKING PLAN
BY:

REV DATE DESCRIPTION
PROJECT NAME:

REHABILITATE RUNWAY 1/19 PHASE 2

SHEET TITLE:

CMT-RFD

PHASING PLAN DETAILS

CMT-RFD


CHECKED:


CMT-ARR

PROJECT NO.: 11258-03-00/06
APRIL 20, 2012
SHEET NO. PPD1

SHEET 6 OF 70 SHEETS

7 6 5 4 3 2





A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON

- B. CONSTRUCT DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.
- C. BUILD NECESSARY EMBANKMENT AT CULVERT/STORM SEWER LOCATIONS AND THEN EXCAVATE AND PLACE PIPE.
- D. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS.

WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE

5. THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2 INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING

RO020

- 6. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND
- 7. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND **ESTABLISHED**

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR

CHICAGO ROCKFORD INTERNATIONAL AIRPORT

MIKE DUNN DIRECTOR



CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS

Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4183

APPROVED AS WORKING PLAN REV DATE DESCRIPTION

REHABILITATE RUNWAY 1/19 PHASE 2

STORMWATER POLLUTION PREVENTION PLAN NOTES

CMT-ARR

DESIGNED: CMT-RFD CMT-RFD

PROJECT NO.: 11258-03-00/06 DATE: APRIL 20, 2012

AREA OF CONSTRUCTION SITE

3. PAVEMENT CONSTRUCTION.

Ε

D

C

В

Α

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 40.0 ACRES OF WHICH 6.0 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION

THE CONSTRUCTION SITE DRAINS INTO THE KISHWAUKEE RIVER VIA OVERLAND FLOW AND

CONTROLS - EROSION CONTROLS AND SEDIMENT CONTROL

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION

BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTION AND PERIMETER SILT FENCE SHALL BE

SHEET NO.

SWN1

SHEET 9 OF 70 SHEETS

INSTALLED AS CALLED OUT IN THE PLANS OR AS DIRECTED BY THE ENGINEER.

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF

THIS PROJECT CONSISTS OF REHABILITATING RUNWAYS, TAXIWAYS, AND CONSTRUCTING A RIAT ROAD AT THE CHICAGO ROCKFORD INTERNATIONAL AIRPORT. THE PROJECT INCLUDES GRADING, EXCAVATION, FILL, TOPSOIL PLACEMENT, PAVEMENT CONSTRUCTION, ELECTRICAL, LANDSCAPING AND OTHER MISCELLANEOUS CONSTRUCTION WORK

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING: 1. PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION

- CONTROL, SUCH AS PERIMETER SILT FENCE AND INLET PROTECTION. 2. EXCAVATION AND EMBANKMENT WILL BE COMPLETED WITHIN THE PROJECT LIMITS.
- 4. FINAL GRADING AND OTHER MISCELLANEOUS ITEMS. 5. PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS SEEDING AND MULCHING. 6. REMOVAL OF TEMPORARY EROSION CONTROL / PROTECTION FACILITIES.


TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.


THROUGH A STORM SEWER SYSTEM


THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION


STORMWATER POLLUTION


PREVENTION PLAN NOTES (SWN1)





















































3

6

5

Н

G

F

Ε

D

В

Α

CHICAGO ROCKFORD INTERNATIONAL AIRPORT

> Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority


AIP Proj: 3-17-0088-XX IL Proj: RFD-4183


DESCRIPTION


REHABILITATE RUNWAY 1/19 PHASE 2


GENERAL NOTES & LEGEND TXYS F. K & M


CHECKED: DLP 11258-03-00/06 APRIL 20, 2012 GNL1






























































8 **RO020** 11'-0" X 11'-0" CONCRETE STRUCTURE BLOCKOUT - SEE NOTES 3 AND 4 LID - SEE NOTE 7 G EXISTING 15" HMA PAVEMENT (TO BE REMOVED BY MILLING - AR800856) NEW 20" PCC PAVEMENT ADJUSTING EXISTING 11" AGGREGATE BASE COURSE NEW 8" AGGREGATE BASE REQUIRED EXISTING 10" SAND SUBBASE DIA. NOTE 1 L#6@8" #8 @ 12" EACH -FACH WAY WAY W/90° HOOK – 2" x 4" SHEAR KEY - TYPICAL REMOVE EXISTING FRAME 8'-0" x 8'-0" MAXIMUM AND LID, CONE SECTION AND SQUARE OPENING - SEE NOTE 12 EXISTING WALL SECTION AS EXCAVATION AS REQUIRED FOR THE ADJUSTMENT UNDISTURBED 4'-0" DIA. (ESTIMATED) 2'-0" JOINT FABRIC EXISTING MANHOLE TO REMAIN EST. MIN. RRWRD SANITARY MANHOLE ADJUSTMENT DETAIL - ADJUSTED NOT TO SCALE ADJUSTED STRUCTURE NOTES: 1. AREAS EXCAVATED UNDER THE PROPOSED RUNWAY PAVEMENT SHALL BE BACKFILLED WITH CRUSHED AGGREGATE BASE COURSE MEETING THE REQUIREMENTS OF AR209 AND COMPACTED TO 95% OF MODIFIED PROCTOR (ASTM D-1557). AGGREGATE BACKFILL SHALL BE CONSIDERED INCIDENTAL TO THE RRWRD SANITARY MANHOLE ADJUSTMENT DETAIL - DEMOLITION 2. AN 8-INCH LIFT OF CRUSHED AGGREGATE BASE COURSE SHALL BE PLACED AND STRUCTURE DEMOLITION NOTES: COMPACTED OVERTOP OF THE PROPOSED ADJUSTED MANHOLE PRIOR TO PCC PAVING. AGGREGATE BASE COURSE SHALL BE CONSIDERED INCIDENTAL TO THE 1. SEE PAVING PLAN AND PROFILE SHEETS FOR THE LOCATION OF THE STRUCTURE TO 3. COORDINATE BLOCKOUT IN FIELD WITH RESIDENT ENGINEER BASED ON FIELD 2. THE EXISTING STRUCTURE IS ESTIMATED TO BE 12-INCHES BELOW THE BOTTOM OF LOCATION OF ADJUSTED MANHOLE. THE SAND SUBBASE. THE AGGREGATE BASE COURSE, SAND SUBBASE AND SUBGRADE MATERIALS SHALL BE REMOVED TO A DEPTH AT LEAST 92-INCHES (7'-8") BELOW THE TOP OF THE PROPOSED PAVEMENT SECTION. 4. EXPANSION MATERIAL SHALL BE PLACED AROUND THE ADJUSTING RINGS AND AT THE EDGES OF THE BLOCKOUT. EXPANSION JOINT MATERIAL SHALL BE PER THE EXPANSION JOINT DETAIL ON SHEET JDT1. EXPANSION MATERIAL SHALL ALSO BE PLACED AROUND THE EXISTING STRUCTURE TO REMAIN, FULL DEPTH OF THE THE PORTION OF THE EXISTING STRUCTURE EXPOSED DURING EXCAVATION SHALL BE REMOVED AND DISPOSED OF OFF AIRPORT PROPERTY. PROPOSED FOUNDATION 5. NO MORE THAN TWO ADJUSTING SHALL BE ALLOWED WITHOUT THE PERMISSION OF 4 THE EXISTING STRUCTURE IS ASSUMED TO BE MADE OF BRICK AND PRECAST BARREL AND CONE SECTIONS WITH AN INSIDE DIAMETER OF 4-0", WITH 12-INCH THICK WALLS. THE DESIGNER SHALL BE NOTIFIED IN THE EVENT THAT THE EXISTING THE RESIDENT ENGINEER. 6. WRAPS AND SEALS PER RRWRD REQUIREMENTS SHALL BE USED TO MAKE WATER STRUCTURE IS LARGER THAN ASSUMED. 5. CARE SHALL BE TAKEN TO NOT DAMAGE THE EXISTING STRUCTURE TO REMAIN. 7. NEW FRAME AND LID SHALL BE NEENAH R-3493-A OR APPROVED EQUAL. LID SHALL 6 ALL EXCAVATION REQUIRED TO LOCATE THE EXISTING STRUCTURE AND TO REACH 8. THE HEIGHT OF THE WALL SECTION IS DEPENDENT UPON THE DEPTH OF THE EXISTING STRUCTURE. THE WALL SHALL BE A MINIMUM OF 2'-0" TALL. 7. THE EXISTING STRUCTURE SHALL BE SAWED AT THE REMOVAL LIMITS. ALL REMOVAL AND DISPOSAL OF THE EXISTING STRUCTURE SHALL BE CONSIDERED 9 THE WALL SECTION AND FLATTOP LID SHALL BEAR EXCLUSIVELY ON THE PROPOSED В FOUNDATION. NO STRESSES SHALL BE IMPARTED ON THE EXISTING STRUCTURE TO REMAIN. INCIDENTAL TO THE ADJUSTMENT. 8. AFTER THE EXISTING STRUCTURE IS LOCATED AND EXAMINED, AT THE CONTRACTOR'S OPTION, A SOLUTION USING PRECAST MATERIALS MAY BE PROPOSED, PROVIDED THE CONTRACTOR PROVIDES SUFFICIENT STRUCTURAL 10. CONCRETE SHALL MEET THE REQUIREMENTS OF ITEM 610 EXCEPT THAT THE CONCRETE SHALL HAVE A COMPRESSIVE STRENGTH OF 4,000 PSI AT 14 DAYS. PROPOSED, PROVIDED THE CONTRACTOR PROVIDES SUPPLIENT STRUCTURAL DESIGN CALCULATIONS FOR REVIEW. THE ENGINEER SHALL HAVE A MINIMUM OF 5 WORKING DAYS TO REVIEW THE PROPOSED ALTERNATIVE. THE PROPOSED ALTERNATIVE SHALL BEAR EXCLUSIVELY ON A FOUNDATION SEPARATE FROM THE 11. STEEL REINFORCEMENT SHALL BE GRADE 60 OF THE SIZES SHOWN 12. IF, BASED ON FIELD CONDITIONS, THE OPENING IS REQUIRED TO BE LARGER THAN $8^{\text{-}}0^{\text{+}}$ x $8^{\text{-}}0^{\text{+}}$, the designer shall be immediately notified. The proposed structure shall not be constructed until the designer has reviewed THE CHANGE IN CONDITION. **SANITARY SEWER MANHOLE ADJUSTMENT DETAIL (SND1)**

Н

G

Ε

D

С

В

Α




MIKE DUNN DIRECTOR



Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX L Proj: RFD-4183



REHABILITATE RUNWAY 1/19 PHASE 2

SHEET TITLE:

SANITARY SEWER MANHOLE ADJUSTMENT DETAIL

	DESIGNED:	DRAWN:	СН	CHECKED: DLP	
	ATI	CMT	-		
		11050 00 0	0.00		
	PROJECT NO.:	11258-03-00/06			
Α	DATE: APRIL 20, 2012				
	SHEET NO.			REVISION	
	SND1				
	SHEET 52	OF 70 SHE	ETS		

