

**GENERAL NOTES CONTINUED**

21. THE RESIDENT ENGINEER SHALL CONTACT PACE'S TRANSPORTATION ENGINEER AT TRANSPORTATION.ENGINEER@PACEBUS.COM AT LEAST 10 DAYS PRIOR TO BEGINNING CONSTRUCTION TO COORDINATE CONSTRUCTION SCHEDULES FOR PACE'S RELOCATION OF THE BUS STOP SHELTER AT THE NORTHWEST CORNER OF IL 171 AND WAVELAND AVENUE, ANY BUS STOP SIGNS, AND ANY BENCHES.
22. THE CONTRACTOR SHALL CONTACT CAZEMBE KABIR OF THE UNITED STATES POSTAL SERVICE AT (312) 983-8336 A MINIMUM OF 2 WEEKS IN ADVANCE OF BEGINNING ADA RAMP IMPROVEMENTS AT THE SOUTHEAST CORNER OF IL 171 AND WINONA STREET, AS WELL AS UPON COMPLETION OF SAID IMPROVEMENTS FOR REMOVAL AND RELOCATION OF THE USPS MAIL COLLECTION BOX BY USPS.
23. THE RESIDENT ENGINEER SHALL CONTACT THE IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4171 AT LEAST 2 WEEKS PRIOR TO BEGINNING WORK FOR LAYOUT.
24. THE RESIDENT ENGINEER SHALL CONTACT JOSEPH WALTER GAYTON III OF DISTRICT 1 BUREAU OF TRAFFIC ELECTRICAL OPERATIONS AT (847) 705-4390 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK TO COORDINATE GAP LOCATIONS OF ELECTRICAL EQUIPMENT WITHIN PROJECT LIMITS.
25. THE CONTRACTOR SHALL USE CARE WHEN PAVEMENT GROOVING NEAR ANY EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE BY THE CONTRACTOR TO EXISTING ITEMS TO REMAIN, INCLUDING PAVEMENT MARKINGS, LOOPS, AND SENSORS, SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

**GENERAL NOTES (CITY OF CHICAGO)**

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "C.U.A.N." (CHICAGO UTILITY ALERT NETWORK) AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF CHICAGO.
3. ALL CATCH BASINS IN THE CITY OF CHICAGO MUST MEET THE DEPARTMENT OF SEWERS' STANDARDS.
4. PERFORATED LIDS SHALL BE PLACED ON ALL MANHOLES AND CATCH BASINS.
5. BENCH MONUMENT LOCATIONS WITHIN THE LIMITS OF THE IMPROVEMENT CAN BE OBTAINED IN SUITE 410 - 333 SOUTH STATE STREET, CHICAGO, IL 60604. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF REPLACEMENT OF ANY BENCH MONUMENT IF DAMAGED OR DESTROYED DURING CONSTRUCTION.
6. ALL BROKEN, CRACKED, WORN OR OTHERWISE DAMAGED OR BICYCLE UNSAFE FRAMES AND LIDS ON SEWER STRUCTURES, SHALL BE REPLACED WITH NEW DEPARTMENT OF SEWERS' STANDARD FRAMES AND LIDS.
7. OPEN LID DRAINAGE STRUCTURES SHALL NOT BE CLOSED, COVERED OR OTHERWISE OBSTRUCTED DURING CONSTRUCTION OF THIS ROADWAY WITHOUT THE WRITTEN PERMISSION FROM THE CITY OF CHICAGO.
8. CITY OF CHICAGO CASTINGS ARE THE PROPERTY OF THE CITY OF CHICAGO AND THE CONTRACTOR SHALL NOTIFY THE CITY FOR REMOVAL AND DISPOSITION OF THE CASTINGS.
9. THE CONTRACTOR SHALL CONTACT DAN GRIGAS OF THE CITY OF CHICAGO AT (312) 744-4815 OR AT DANIEL.GRIGAS@CITYOFCHICAGO.ORG A MINIMUM OF 2 WEEKS IN ADVANCE OF BEGINNING ADA RAMP IMPROVEMENTS AT THE NORTHEAST CORNER OF IL 171 AND BELLE PLAINE AVENUE IN ORDER TO COORDINATE PROPOSED HANDHOLE WORK.
10. UNRESTRICTED ACCESS SHALL BE PROVIDED AT ALL TIMES TO THE FEEDER MAIN ISOLATION VALVES MAINTAINED BY THE CITY OF CHICAGO'S DEPARTMENT OF WATER MANAGEMENT. THE RESIDENT ENGINEER SHALL CONTACT MR. ALBERT WTORKOWSKI OF THE DEPARTMENT OF WATER MANAGEMENT AT ALBERT.WTORKOWSKI@CITYOFCHICAGO.ORG OR BY PHONE AT (312) 744-5070 TO SCHEDULE FINAL INSPECTION OF ANY ADJUSTED FACILITIES.

 REVISED SHEET 6-4-2018

FILE NAME =	USER NAME = toriafm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, HIGHWAY STANDARDS, &amp; GENERAL NOTES IL 171 &amp; I-90 / I-94</b>	F.A. RTÉ.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
p:\IL\084EBIDINTEG\illinois.gov\PWIDOT\Documents\IDOT Offices\District 1\Projects\DI07417\Design\DI07417-sht-genote.dgn		DRAWN	REVISED -			VAR.	3056B-R5-2	COOK	73	3	
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -			CONTRACT NO. 62D65					
	PLOT DATE = 5/8/2018	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO
						ILLINOIS FED. AID PROJECT					