



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 4, 2018

SUBJECT: FAP Route 311 (IL 71)
Project NHPP-C13D(332)
Section (1)R,I
Kendall County
Contract No. 66D24
Item No. 186, June 15, 2018 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 35 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Acting Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Kevin Marchek, Region 2, District 3; Tim Kell

JW/ck

POROUS GRANULAR EMBANKMENT

Description. This work consists of backfilling box culverts or three-sided structures with granular materials. This work shall be performed at locations shown on the plans or as directed by the Engineer. The quantity of backfill for each culvert is shown in a plan schedule and the work is shown in the Box Culvert Backfilling Detail in the plans.

Backfilling shall be performed according to Article 502.10. The backfill material shall meet the requirements of Article 1004.05, except the gradation shall be CA-07 or CA-11.

Method of Measurement. This work will be measured for payment in cubic yards compacted in place. Additional material required to backfill excavation outside the limits shown on the plans will not be measured for payment.

Basis of Payment. This work will be paid for at the contract unit price per cubic yard for POROUS GRANULAR EMBANKMENT.

TEMPORARY PAVEMENT

Description. The Contractor has the option to install either hot-mix asphalt or Portland cement concrete temporary pavement. This work shall consist of furnishing all labor, equipment and materials to install and remove temporary pavement, including hot-mix asphalt, prime coat and sub-base granular material, Portland cement concrete, and saw cutting the existing pavement to a vertical edge in accordance with applicable portions of Sections 311, 406, 420 and 440 of the Standard Specifications and at the locations shown in the plans.

Method of Measurement. This work will be measured for payment by square yards.

Basis of Payment. This work will be paid for at the contract unit price per square yard for TEMPORARY PAVEMENT.

TEMPORARY DRAINAGE

The Contractor is required to provide and maintain temporary drainage. Unless otherwise noted, proposed drainage items are to be used for temporary drainage. Adjustment to inlets or manholes from temporary elevations to final elevations will be included in the cost of the proposed drainage structures.

Lids used for proposed temporary connections shall be designated Temporary Lids, of the type specified and shall be furnished, installed, maintained, and removed as specified, except the lid need not be new. When a used lid is furnished, the Engineer will visually inspect the lid for acceptance. This work will be paid for at the contract unit price per each for LIDS, of the type specified.

See the Staging Plans and the Temporary Drainage Schedule for temporary drainage items.

Revised 6-4-18