

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 342	530CRC-PP	COOK	16	6

CONTRACT 62962

NORTHBOUND IL RTE. 53 EXTENSION

PATCH LOCATION NUMBER	STATION	LANE	Northbound				
			SIZE (L X W)			AREA (SQ. YD.)	TYPE
1	445+17	3	265	x	12	353.3	IV
2	444+50	1	100	x	12	133.3	IV
3	444+50	2	100	x	12	133.3	IV
4				x			
5	447+67	1	50	x	6	33.3	IV
6	448+50	1	40	x	12	53.3	IV
7				x			
8	453+40	2	40	x	12	53.3	IV
9	453+40	3	40	x	12	53.3	IV
10	454+40	3	30	x	12	40.0	IV
11	458+23	3	15	x	12	20.0	III
12	462+79	2	8	x	12	10.7	II
12A	462+79	3	8	x	12	10.7	II
13	463+50	2	20	x	12	26.7	IV
14	466+61	1	12	x	12	16.0	III
15	466+67	2	42	x	12	56.0	IV
16	469+95	1	20	x	12	26.7	IV
17	469+95	2	20	x	12	26.7	IV
18	471+55	2	20	x	12	26.7	IV
19	471+53	1	6	x	12	8.0	II
20	471+78	1	6	x	12	8.0	II
21	474+77	2	15	x	12	20.0	III
22	475+54	1	8	x	12	10.7	II
23	475+96	2	12	x	12	16.0	III
24	476+47	2	25	x	12	33.3	IV
25	477+17	2	15	x	6	10.0	II

PATCH LOCATION NUMBER	STATION	LANE	Northbound				TYPE
			SIZE (L X W)			AREA (SQ. YD.)	
26	478+00	2	30	x	12	40.0	IV
27	479+25	2	40	x	6	26.7	IV
28	479+37	1	15	x	12	20.0	III
29	479+79	2	8	x	12	10.7	II
30	480+97	1	6	x	12	8.0	II
31	481+52	2	15	x	12	20.0	III
32	482+02	1	8	x	12	10.7	II
33	482+62	1	35	x	12	46.7	IV
34	482+62	2	35	x	12	46.7	IV
35	483+74	1	8	x	12	10.7	II
36	486+13	3/Ramp*	12	x	12	16	III
37	486+09	2	8	x	12	10.7	II
38	486+58	1	20	x	12	26.7	IV
39	486+58	2	20	x	12	26.7	IV
40	486+85	1	10	x	12	13.3	II
41	487+60	1	30	x	12	40.0	IV
42	489+45	1	10	x	12	13.3	II
43	489+45	2	10	x	12	13.3	II
44	489+76	1	12	x	12	16.0	III
45	489+76	2	12	x	12	16.0	III
46	491+59	1/Ramp*	12	x	12	16.0	II
47	491+60	2/Ramp*	12	x	12	16.0	II

* SEE JOINT DETAILS (SHEET #11). THE COST OF PAVEMENT RELIEF JOINT SHALL BE INCIDENTAL TO CLASS A PATCHING.

- CENTER LINE OF IL RTE. 68 (DUNDEE) : STA. 435+44
- ALL STATIONINGS ARE CENTER OF EACH PATCHING LOCATIONS.

ILLINOIS DEPARTMENT OF TRANSPORTATION

**IL ROUTE 53 EXTENSION
PAVEMENT PATCHING SCHEDULE
1 OF 2**