SCHEDULE OF QUANTITIES

87900205 DRILL EXISTING HEAVY DUTY HANDHOLE EACH LOCATION 9 576+20 REMARKS NW QUAD OF INTERÆCTION 1 NW Quad, Raised Island See Detector Loop Detail Sheet 10 TOTAL 88600600 DETECTOR LOOP REPLACEMENT FOOT LOCATION REMARKS 405 576+10 20'×6' (4) 405 575+80 20'x6' (4) 810 TOTAL X0324885 CONDUIT INSTALLED, 1° DIA., NON-METALLIC <u>FOOT</u> <u>LOCATION</u> 380 NW Quad of Intersection REMARKS Outside Rt Turn Lane Shldr (8 runs) 38Ø TOTAL X0324887 CONDUIT INSTALLED, 2 1/2" DIA., NON-METALLIC EOOI LOCATION 48 NW Quad of Intersection See Detector Loop Detail Sheet 48 TOTAL X4402810 ISLAND SURFACE REMOVAL AND REPLACEMENT SO FI LOCATION
30 NW Quad, Raised Island REMARKS See Detector Loop Detail Sheet 30 TOTAL X6330103 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, TANCENT EACH LOCATION 1 551+87 - 552+37 LT REMARKS SOUTHBOUND 1 TOTAL ZØØ28415 GEOTECHNICAL REINFORCEMENT SOLYD LOCATION REMARKS
171.1 North and Southbound Patches Directed by Engineer
188.2 NW Quad of Intersection Below Shidr in Return
300 Bridge Shoulder Runaround Directed by Engineer 659.3 TOTAL Z0028700 GRANLAR SUBGRADE REPLACEMENT REMARKS 34 North and Southbound Patches Directed by Engineer 34 TOTAL Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 EACH LOCATION SOUTHBOUND-ST 1 1 552+58 LT NORTHBOUND-ST 1 2 TOTAL Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH LOCATION REMARKS
1 549+20 RT SOUTHBOUND-ST 2 1 552+58 LT NORTHBOUND-ST 2 2 TOTAL

REVISIONS NAME	DATE	ILLINOIS	DEPARTMENT	OF	TRANSPORTATION
		SCALE: VERT. HORIZ.			DRAWN BY
		DATE			CHECKED BY