COUNTY FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

* 14RS-2,122RS-3 & (123NRS,14)BR

CONTRACT NO. 70134 D-95-064-00

BILL OF MATERIAL (ONE HEADWALL) Bar No. Size Length (ft) Shape

EACH

F.A.P. RT. 749 SEC. 14RS-2,122RS-3&(123NRS,14)BR LOADING HS20 STR. NO. 023-8313

NAME PLATE DETAIL

* SEE HIGHWAY STANDARD 515001-02 FOR DIMENSIONS

PRICE PER "EACH" FOR "NAME PLATES"

NAME PLATE WILL BE PAID FOR AT THE CONTRACT UNIT

BOX CULVERT END SECTIONS (CAST IN PLACE)

2 @ 6.0' X 2.0'

STA. 8+76 NO SKEW

STRUCTURE NO. 023-8313

REINFORCED CONCRETE HEADWALL DETAILS


ITEM Box Culvert End


Sec. Culvert No.

AND PLACEMENT.

DETAIL OF BOX CULVERT END SECTION **A.R. BOX CULVERT TYPE 2 @ 6.0' X 2.0'**

STA. 8 + 76 (CULVERT NO. 1)







SECTION A - A

* CUT TO FIT








- All bars should be rounded and shall conform to the requirements of Art. 1006.10 of Standard Specs.
- Class SI Concrete shall be used throughout.
- The Precast Concrete Box Culvert Sections shall conform to the requirements of AASHTO M273.
- All dimensions are in FEET (')-INCHES (") unless otherwise noted.
- Concrete and Rebar quantities and lengths calculated for the cast-in-place End Sections will vary based on the precast box culverts supplied.
- End Sections will be paid for at the contract unit price each for BOX CULVERT END SECTION CULVERT NO., as outlined in Art, 540.08, which prices shall include all concrete, rebar, and all other items necessary to complete the proposed
- Drain holes shall be provided in accordance with Art. 503.12.

END VIEW



- Drawings not to scale.

#4b-b2 @ 1'-6" cts. #4v₁ -v₆ @ 1'-0" cts.

PLAN

ILLINOIS DEPARTMENT OF TRANSPORTATION

CULVERT DETAILS

SCALE: VERT.

DRAWN BY JDC CHECKED BY