

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
315	34-5	HANCOCK	612	242
STA.		TO STA.		
FED. ROAD DIST. No.	ILLINOIS	FED. AID PROJECT		

LIGHTING GENERAL NOTES:

1. QUANTITIES OF PUSHED CONDUIT, ELECTRICAL CABLE AND TRENCH WHERE INDICATED ON THE PLANS, ARE APPROXIMATIONS ONLY. THE CONTRACTOR SHALL FIELD VERIFY ALL LENGTHS AND SHALL INSTALL RACEWAYS IN COMPLETE CONFORMANCE WITH SPECIFIED REQUIREMENTS.
2. EQUIPMENT GROUND CONDUCTORS SHALL BE SPLICED AND BONDED TO EACH LIGHT POLE.
3. COMMONWEALTH EDISON COMPANY SHALL BE CONTACTED AS SOON AS POSSIBLE AND NOTIFIED OF PENDING SERVICE CONNECTIONS AND INSTALLATIONS TO INSURE CONTINUITY OF NIGHT TIME HOURS OF LIGHTING OPERATION.
4. NO EQUIPMENT OR MATERIAL SHALL BE DELIVERED TO THE JOB SITE PRIOR TO THE APPROVAL AND INSPECTION BY THE ENGINEER. ANY EQUIPMENT OR MATERIAL DELIVERED TO THE JOB SITE PRIOR TO APPROVAL AND INSPECTION SHALL BE REMOVED FROM THE JOB SITE AT THE CONTRACTOR'S EXPENSE.
5. THE PROPOSED LIGHTING CONTROL CABINET SHALL BE INSTALLED WITHIN THE RIGHT-OF-WAY WITH THE EXACT LOCATION TO BE CONFIRMED IN THE FIELD.
6. PROVIDE A 5/8" DIA. X 10' LONG GROUND ROD AT THE BASE OF EACH LIGHT UNIT.
7. THE ELECTRICAL WORK SHALL BE IN CONFORMANCE WITH THE NATIONAL AND LOCAL ELECTRICAL CODES.

LIGHTING BILL OF MATERIALS			
CODE NO.	ITEM	UNIT	QUANTITY
XX220000	REMOVE EXISTING LIGHTING	EACH	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**LIGHTING GENERAL NOTES
AND
LIGHTING BILL OF MATERIALS**

SCALE: DRAWN BY: RG
DATE: MARCH 10, 2006 CHECKED BY: JAC

DGN-SPEC
DATE-TIME
*REF01