



		CONTRACT	NO. 74	880
F.A RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
•	**	MARION	17	8
STA.		TO STA.		

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

\* VARIOUS ROUTES
\*\* D7 SIGNAL MODERIZATION 2006-2

## BILL OF MATERIALS

## SB U.S. RTE. 51 (POPLAR ST.) & BROADWAY

<u>ITEM</u>	UNIT	QUANTITY
PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	2317.0
PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH. SPECIAL	SQ FT	119.0
SIDEWALK REMOVAL	SQ FT	2317.0
SIDEWALK REMOVAL (SPECIAL)	SQ FT	119.0
SIGN PANEL-TYPE 2	SQ FT	36.0
SERVICE INSTALLATION, TYPE B	EACH	1.0
CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	204.0
CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	57.0
CONDUIT, AUGERED 4" DIA., PVC	FOOT	163.0
HANDHOLE	EACH	4.0
DOUBLE HANDHOLE	EACH	1.0
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	261.0
FULL-ACTUATED CONTROLLER AND TYPEE III CABINET	EACH	1.0
ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	320.0
ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	677.0
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	176.0
TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	2.0
TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	1.0
STEEL MAST ARM ASSEMBLY AND POLE, 16 FT	EACH	1.0
STEEL MAST ARM ASSEMBLY AND POLE, 20 FT	EACH	1.0
STEEL MAST ARM ASSEMBLY AND POLE, 38 FT	EACH	1.0
CONCRETE FOUNDATION, TYPE A	FOOT	9.0
CONCRETE FOUNDATION, TYPE D	FOOT	3.0
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	21.0
CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	16.5
TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	11.0
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1.0
REMOVE EXISTING HANDHOLE	EACH	4.0
REMOVE EXISTING CONCRETE FOUNDATION	EACH	5.0
ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	613.0
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2.0
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6.0
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1.0
SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1.0
PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	4.0

REVISIONS ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS

SB U.S. 51 & BROADWAY

PLOT DATE = 5/22/2006 File NAME = \$FILEL\$ PLOT SCALE = \$SCALE\$ USER NAME = swartzrw

△ Rev. Sheet 5-31-06

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY