

SIDE VIEW

FRONT VIEW

J:\PROJECTS\PROJECTS 2003\CEDARRD\LIGHTING\DETAILS\2005_07_20_FINAL_FINAL\E-12_CNTRL_WIRING_DETAIL.DGN

D-91-467-97		22757		
STA.		TO STA.		
0369	97-000-25-00 BR	WILL	156	104
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO

- 1. FOUNDATION SIZE SHALL BE COORDINATED WITH CABINET SIZE AND MANUFACTURER.
- 2. IN FRONT OF CONTROL CABINET DOOR, REMOVE VEGETATION AND 2" TOP SOIL. LEVEL THE AREA AND ON TOP PLACE LENGTH WISE PARALLEL TO CONTROL CABINET (NEMA 3R) A CONCRETE PAD 36" X 60" X 4" MINIMUM SIZE. THE COST OF LABOR AND MATERIALS ARE INCLLIDED IN THE COST OF THE CONTROLLER.
- DOOR SHALL BE CONSTRUCTED FROM THE SAME TYPE OF MATERIAL AND THICKNESS AS CABINET.
- 4. DOOR SMALL BE EOUIPPED WITH THREE POINT LATCHING MECHANISM WITH NYLON RDLLERS AT TOP AND BOTTOM.
- 5. DOOR HINGE SHALL BE A HEAVY GUAGE CONTINEOUS HINGE WITH A 1/4" DIA. STAINLESS STEEL HINGE PIN.
- 6. ALL EXTERNAL HARDWARE SHALL BE STAINLESS STEEL
- 7. CONTROL WIRING TO BE #12 AWG, 600V, TYPE "SIS" GRAY SWITCH BOARD WIRE, STRANDED COPPER.
- 8. METER BOX SHALL BE MOUNTED ON THE SIDE OF CONTROL CABINET NEAREST TO THE SERVICE POLE.
- 9. CABINET SHALL BE PRIMED AND PAINTED AS SPECIFIED IN THE IDOT STANDARD SPECIFICATIONS.
- 10. THE HEADS OF CONNECTORS SCREWS SHALL BE PAINTED WHITE FOR NEUTRAL BAR CONNECTION AND GREEN FOR GROUND BAR CONNECTION.
- 11. ALL WIRING WITHIN THE CABINET SHALL BE COLOR CODED AS INDICATED:

B= BLACK

W= WHITE Y= YELLOW G= GREEN

- 12. PROVIDE SEALING GROMMETS FOR ALL OPEN WIRING EXTENDED FROM DEVICES IN BOXES OR CABINETS WITHIN THE CONTROL CABINET.
- 13. ALL WIRING SHALL BE NEATLY DRESSED AND SUPPORTED.
- 14. THE CONTROLLER SHALL BE CONSTRUCTED TO U.L. STD. 508 AND BEAR THE U.L. LABEL "ENCLOSED INDUSTRIAL CONTROL PANEL".
- 15. 12" X 16" STAINLESS STEEL EXTERIOR NAMEPLATE SHALL BE ENGRAVED TO "STATE OF ILLINOIS LIGHTING CONTROLS" UNLESS OTHERWISE SPECIFIED.

ILLINOIS DEPARTMENT OF TRANSPORTATION

LIGHTING CONTROLLER SINGLE DOOR CONTROLLERS "A", "B", AND "WE"

SCALE: NONE DATE: JULY 20, 2005

DRAWN BY: KGP/MAE DESIGNED BY: MAE/KGP CHECKED BY: PKG