



## General Notes

- 1. ALL PERMANENT EROSION CONTROL MEASURES SHALL BE CONSTRUCTED AS SOON AS PRACTICAL.
- 2. TEMPORARY SEEDING SHALL BE PLACED WHEN THE GROUND HAS BEEN DISTURBED AND PLACEMENT OF PERMANENT SEEDING IS NOT PRACTICAL OR AS DIRECTED BY THE ENGINEER.
- 3. PLACE SEEDING, CLASS 2A IN AREAS USING MULCH, METHOD 2 AND EROSION CONTROL BLANKET.
- 4. CONTACT THE DISTRICT 4 LANDSCAPE
  ARCHITECT AT (309) 671-4484 FOR TREE PLANTING
  LOCATIONS AT LEAST 2 WEEKS PRIOR TO
  PLANTING TREES.





CHECKED BY

REVISIONS NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION	
		EROSION CONTROL & LANDSCAPING PLANS	
		SCALE: VERT. DRAWN BY	