

AR ROAD CULVERTS / CLSM

CENTER LOCATION BY STATION	TYPE A.R. or S.R.	COMMENTS	CULVERT REQUIRED (FT)					END SECTIONS REQUIRED					CLSM	AGG. SURF.
			R.C.C.P. TYPE 1					R.C.C.P. TYPE 1					REQUIRED	CSE. TY B
			18" EQ	24"	24" EQ	30" EQ	10'x5' BOX	18" EQ	24"	24" EQ	30" EQ	10'x5' BOX	(CU. YD.)	(TONS)
21+00	A.R.	BOX CULVERT #1	--	--	--	--	45'	--	--	--	--	2	56	22
33+61	A.R.	SINGLE CULVERT	40'	--	--	--	--	1	--	--	--	--	32	5
59+90	A.R.	TWIN CULVERTS	--	--	--	32' 32'	--	--	--	--	2	--	28	15
88+99	A.R.	TWIN CULVERTS	--	--	32' 32'	--	--	--	--	2	--	--	25	13
109+37	A.R.	TWIN CULVERTS	--	--	--	32' 32'	--	--	--	--	2	--	25	15
128+52	A.R.	SINGLE CULVERT	--	32'	--	--	--	--	2	--	--	--	9	5
150+34	A.R.	BOX CULVERT #2	--	--	--	--	45'	--	--	--	--	2	47	18
220+22	A.R.	TWIN CULVERTS	--	--	--	40' 40'	--	--	--	--	2	--	28	17
305+20	A.R.	TWIN CULVERTS	--	--	40' 40'	--	--	--	--	2	--	--	28	12
317+86	A.R.	SINGLE CULVERT	--	--	32'	--	--	--	--	2	--	--	11	6
	TOTALS		40'	32'	176'	208'	90'	1	2	10	12	4	289	128

RIPRAP SCHEDULE

STONE DUMPED RIPRAP, CLASS A4 28100807
FILTER FABRIC FOR USE WITH RIPRAP 28200100

CENTER LOCATION BY STATION	LOCATION LT OR RT	COMMENTS	RIPRAP TONS ALLOWED	FILTER FABRIC SQ YD
21+00	RT	BOX CULVERT #1 DISCHARGE	55	94
59+90	LT	FIELD DRAINAGE AT NEW CULVERT	10	16
99+93	LT	EXISTING CULVERT REPAIR	10	12
99+93	RT	EXISTING CULVERT REPAIR	14	24
109+37	RT	TWIN CULVERT DISCHARGE	10	19
150+34	RT	BOX CULVERT #2 DISCHARGE	24	41
167+07	RT	EXISTING CULVERT REPAIR	24	41
220+22	RT	TWIN CULVERT DISCHARGE	10	13
305+20	LT	EXISTING CULVERT REPAIR	10	16
317+86	LT	SINGLE CULVERT	10	9
		TOTALS	177	286

SHAPING ROADWAY
SCHEDULE OF SHAPING ROADWAY
(LR 212000)

CURVE #	PI STATION	FEET	UNITS
1	119+65.89	1200	12
2	137+75.54	1200	12
3	156+96.73	1000	10
4	165+68.99	900	9
5	270+67.21	1000	10
6	298+39.90	1100	11
TOTALS		6400	64

SR ROAD CULVERTS

EXISTING SR CULVERT	COMMENTS	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM		AGG. SURF. CSE. TY B
		12" RS	15" RS	(TONS)
STA 53+59 (15"x44" CMP)	REPLACE WITH SAME	--	44	10
STA 80+02 (15"x46" CMP)	REPLACE WITH SAME	--	46	10
STA 137+18 (12"x30" CMP)	REPLACE WITH SAME	30	--	10
TOTALS		30	90	30

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01-00109-00-FP	WAYNE	10	3
FAS ROUTE	FAS 797	NORTH ENTERPRISE	
ILLINOIS PROJECT	RS-797(121)		
CONTRACT NO.	95468		