
FAU	SECTION	COUNTY	TOTAL SMETS	SHEET MG
9177	00-00007-01-PV	ST CLAIR	40	10
STA		TO STA.		
EXIS	TING CONDITIONS	1		
CONTR	ACT NO. 97263			

SEIBERT ROAD		VEMENT MARKING	
STATION TO STATION		4" MARKINGS SKIP-DASH YELLOW (FOOT)	8" MARKINGS CROSS WALK WHITE (FOOT)
2+90,00	17+65.00	370	
16+74.00			51.0
PARK DR.			136
DIAMOND CT.			96
TO	TAL	370	283

RA	SED	REFLECTIV	E PAVEMENT MARKER SCHEDULE
		:	SEIBERT ROAD
STATIO	n TO S	STATION	RAISED REFLECTIVE PAVEMENT MARKERS TWO-WAY AMBER (EACH)
2+90.00	то	17+65.00	20
	TOTAL :		20



	SIGNING SCHEDULE						
LOCATION	TELESCOPING SIGN SUPPORT	SIGN PANEL	REMARKS				
STATION	(FEET)	(SQ FT)					
SEIBERT ROAD			·····				
11+80, 00, 55, 50' RT	13.0	3. 75	BIKE ROUTE W/ DIR. ARROW/(BACK)	(D11-1)/(M7-1)			
12+00, 00, 41, 00' RT	12.0	7.00	BIKE ROUTE W/ BIKE ROUTE ENDS	(D11-1)/(M4-12)			
TOTAL	25.0	10.75		<u> </u>			

PERIMETER EROSION BARRIER SEIBERT ROAD			
STATION	1 TO	STATION	PERIMETER EROSION BARRIER
<u> </u>			(FEET)
3+10.00 RT	TO	4+00.00 RT	90
8+00.00 LT	TO	13+00.00 LT	500
TOTAL :			590

REVISIONS DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION		
		SCHEDULE OF QUANTIT	IES	
		SEIBERT ROAD SECTION 00-00007-01-PV		
		ST CLAIR COUNTY		
		SCALE: VERT. DRAWN	ВҮ	
		DATE CHECKE	D BY	