BRIDGE REPLACEMENT & REHABILITATION PROGRAM DETAIL PLANS FOR

PROPOSED BRIDGE

F.A.S. 782 (KEYESPORT ROAD) OVER FLAT BRANCH SECTION 05-00084-00-BR & SECTION 05-00079-00-BR **CLINTON & BOND COUNTY**

PROJECT: BRS-782(118)

JOB NO: C-98-339-06

COUNTY

INDEX OF SHEETS

- COVER SHEET
 SUMMARY OF QUANTITIES AND TYPICAL CROSS SECTIONS PLAN AND PROFILE OF EXISTING AND PROPOSED ROADWAY
- DETOUR MAP GENERAL PLAN AND ELEVATION
- ABUTMENT DETAILS PIER DETAILS
- P.P.C. DECK BEAM SUPERTRUCTURE
- P.P.C. DECK BEAM DETAILS STANDARD CR-TSM
- EXISTING PLANS: GENERAL PLAN AND ELEVATION EXISTING PLANS: DECK BEAMS
- EXISTING PLANS: SUBSTRUCTURE

HIGHWAY STANDARDS: 280001-02 630001-06

631032-02

702001-06 BIR 21-6

DESIGN CLASSIFICATION

DESIGN GUIDLINES 3R MAJOR COLLECTOR DESIGN SPEED = 50 M.P.H. DESIGN A.D.T. = 1,500 (2025)

UTILITIES:

CALL J.U.L.I.E. BEFORE YOU DIG

ELECTRIC:

SOUTHWESTERN ELECTRIC COOP, INC. GREENVILLE, IL (618) 664-1025

WATER

CARLYLE NORTH WATER CO. CARLYLE, IL (618) 594-2508

SEWER

VILLAGE OF KEYESPORT (618) 749-5511

THESE PLANS WERE PREPARED BY ME OR BY A FULL TIME MEMBER OF MY STAFF WORKING UNDER MY PERSONAL SUPERVISION.



PROJECT LOCATION


WARNING

CALL BEFORE YOU DIG

THE EXISTING STRUCTURE IS A THREE SPAN PRECAST PRESTRESSED CONCRETE DECK BEAM BRIDGE ON SPILL THRU ABUTMENTS AND PILE BENT PIERS. THE EXISTING STRUCTURE IS 114'-6" BACK TO BACK OF ABUTMENTS AND IS 27'-0" OUT TO OUT OF THE EXISTING DECK.


PROPOSED STRUCTURE NO. 014-3000 STATION 66+73

COUNTY ENGINEER __ DATE //31/06_ ILLINOIS P.E. # 62-32252 EXPIRES 11/30/07



LOCATION MAP

NET LENGTH OF PROJECT = 580 FEET OR 0.110 MILES






ROUTE NO COUNTY F.A.S. 782 05-00084-00-BR 05-00079-00-BR (KEYESPORT RD) & BONE FEDERAL AID PROJECT PROJECT NO. 97272

LOCATION OF SECTION





CONTRACT NO: 97272