

CONTRACT NO. 98980

F.A.P. RTE.	SECTION	(OUNTY	,	TOTAL SHEETS	SHEET NO.
853	9RS-4		HAMILT	ON	12	11
STA.		TO	STA.			
FED. RO	AD DIST. NO.	ILLINOIS	FED.	AID	PROJECT	



TYPICAL CENTERLINE, NO PASSING ZONE LINE (NPZ) & EDGELINE MARKINGS 2-LANE PAVEMENT




*DIAGONAL SPACING

** PLACE THE FIRST ARROW EVEN WITH THE BEGINNING OF THE TURN BAY. PLACE ANOTHER ARROW 18' BACK FROM THE STOP BAR. IF REQUIRED, ADD ADDITIONAL ARROWS TO MAINTAIN A MAXIMUM OF 80' SPACING.

NOTES:

- 1. OMIT EDGELINE THRU SIDE ROADS.
- 2. TAPER RATES, LANE WIDTHS, AND STORAGE LENGTHS AS SHOWN ON THE PLANS.
- 3. WHEN MEDIANS ARE PRESENT, PLACE A SINGLE YELLOW STRIPE AROUND ITS PERIMETER.



NOT TO SCALE

REVISIO NAME MMO	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION
DRM	08-04	TYPICAL APPLICATON OF PAVEMENT MARKINGS SHEET 1 OF 2
		SCALE: VERT. DRAWN BY

CHECKED BY