* SEE MODIFY SIGN PANEL NOTE.

LEGEND

L-858L, LOCATION SIG

L-858L, LOCATION SIGN (YELLOW LEGEND AND BORDER ON A BLACK BACKGROUND)

27 →

L-858Y, DIRECTION SIGN (BLACK LEGEND ON A YELLOW BACKGROUND)

20-2

L-858R, MANDATORY SIGN (WHITE LEGEND ON A RED BACKGROUND)

DUCT NOTE:

THE CONTRACTOR WILL INSTALL THE PROPOSED DUCT AT THE LOCATIONS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE DETAILS AND THE SPECIFICATIONS. THE CONTRACTOR WILL SET THE TOP ELEVATION OF THE CONCRETE DUCT TO PROVIDE FOR THE INSTALLATION OF THE UNDERDRAIN.

THE PROPOSED DUCTS WILL BE PAID FOR UNDER ITEM:
AR110502 "2-WAY CONCRETE ENCASED DUCT_______ 153 L.F

DUCT REMOVAL_NOTE:

TWO DUCTS (41 L.F. EACH) WILL BE EXCAVATED AND REMOVED FROM THE AIRPORT AS PART OF THIS PAY ITEM. THE CONTRACTOR WILL FILL THE HOLE IF BELOW FINISHED GRADE AND COMPACT TO PREVENT FUTURE SETTLEMENT. THE CONTRACTOR MUST HAVE ALL ACTIVE TAXIMAY/RUNWAY CIRCUITS IN WORKING ORDER EITHER BY JUMPER OR PROPOSED CABLING BEFORE THESE DUCTS WILL BE REMOVED. EXCAVATION, REMOVAL AND DISPOSAL OF THE EXISTING CONCRETE DUCT WILL BE PAID FOR UNDER

AR110900 "REMOVE DUCT"______ 82 L.F.

LIGHT RELOCATION NOTE


THE CABLE USED TO RECONNECT ALL LIGHTING CIRCUITS WILL BE #8 5000 V., 1/C UNDERGROUND CABLE IN UNIT DUCT. THIS WILL BE PAID FOR UNDER:

AR108158 1/C #8 5 KV UG CABLE IN UD____ 6,092 L.F.


THE CABLE USED TO CONNECT THE REIL AND PAPI CIRCUITS WILL BE 2/C #4 500 V UNDERGROUND CABLE IN UNIT DUCT AND WILL BE PAID FOR UNDER:

AR108554 2/C #4 600V UG CABLE IN UD____ 1,091 L.F.









DETAIL "B"
"NOT TO SCALE"

LIGHT/SIGN REMOVAL NOTES

ALL EXISTING TAXIWAY LIGHTS AND SIGNS THAT ARE DESIGNATED FOR REMOVAL WITH AN "X" WILL BE REMOVED. THE LIGHTS, SIGNS AND THEIR ISOLATING TRANSFORMERS WILL BE TURNED OVER TO THE AIRPORT MANAGER. THE LIGHT/SIGN STAKES AND BASES WILL BE REMOVED AND DISPOSED OF OFF THE AIRPORT SITE AT THE CONTRACTOR'S OWN EXPENSE.

THE HOLE LEFT FROM THE LIGHT/SIGN REMOVAL WILL BE FILLED IN WITH EARTH AND COMPACTED TO PREVENT FUTURE SETTLEMENT. THE DISTURBED AREAS WILL BE FERTILIZED AND SEEDED IN ACCORDANCE WITH THE SPECIAL PROVISIONS.

THE EXISTING RUNWAY CABLES WILL BE ABANDONED IN PLACE UNLESS IT CONFLICTS WITH THE INSTALLATION OF A PROPOSED LIGHT OR CABLE, THEN IT WILL BE REMOVED AT NO ADDITIONAL, COST TO THE CONTRACT.

REMOVAL OF THE EXISTING LIGHTS, SIGNS AND ISOLATING TRANSFORMERS WILL BE PAID FOR UNDER ITEMS:

AR125901 "REMOVE STAKE MOUNTED LIGHT" 2 EACH
AR125902 "REMOVE BASE MOUNTED LIGHT" 1 EACH
AR125904 "REMOVE TAXI GUIDANCE SIGN" 2 EACH.

MODIFY SIGN PANEL NOTE

THE TAXI GUIDANCE SIGN LABELED TS4-41 AS SHOWN ON THE PREVIOUS SHEET SHALL HAVE THE SIGN PANELS REMOVED AND REPLACED AS DETAILED ON THIS SHEET. THERE ARE TWO EXISTING SIGN PANELS ON THIS SIGN THAT READS "84". THESE SIGN PANELS WILL BE REPLACED WITH SIGN PANELS THAT READ "A1". THE SIGN PANEL WILL BE DESIGNATED AS A LOCATION SIGN, THEREFORE THESE SIGNS HAVE YELLOW INSCRIPTIONS ON A BLACK BACKGROUND WITH A YELLOW BORDER.

THE CONTACTOR WILL VERIFY THE SIGN MANUFACTURER. THE CONTRACTOR WILL REMOVE THE EXISTING SIGN PANELS AND TURN THEM OVER TO THE AIRPORT. THE CONTRACTOR WILL FURNISH AND INSTALL THE NEW SIGN PANELS FOR THE SIGN. THE SIGN PANELS TO BE REPLACED WILL BE PAID FOR UNDER ITEM:

AR125470 MODIFY EXISTING SIGN PANEL______ 1 EACH.

DATE REVISION BY



Scot. NOT TO SCALE.

Date 02/10/06

LAYOUT K.D.M. 02/10/06

DRAWN M.D.R. 02/10/06

Hanson Professional Services inc.
1525 South Skirk Street
Sonthaled. Blinds 62793-2885

EXTEND
TAXIWAY "A"
PROPOSED
ELECTRICAL

84 84 of 224 sheet

APR 13, 2006 10:01 AM CAH